

July 20, 2021: 04:45-05:30 AM Hawaiian Standard Time (Track 5, Session 4.5.2)

Demonstrating the Value of Systems Engineering as the Professional Standard of Care

Oliver Hoehne, PMP, CSEP, CSM Technical Fellow, Systems Engineering WSP USA oliver.hoehne@wsp.com

www.incose.org/symp2021







Problem Statement & Offered Solution

- Project Risk and Liability
- SE as Liability Protection and Risk Mitigation Strategy
- Background & Introduction
- Systems Engineering Challenges Faced
- Systems Engineering Objectives
- Systems Engineering Activities Performed
- Summary, Achieved Outcomes & Conclusion

PROBLEM STATEMENT EXAMPLE: THE "BIG DIG" PROJECT

- Central Artery/Tunnel Megaproject in Boston, MA
- Commonly known as the Big-Dig project
- Rerouted Interstate 93 (I-93) running through the heart of the city into a 1.5-mile tunnel
- Designed and built between 1982 and 2007
- Most expensive highway project in the US at the time (21.5 billion in 2020 US dollars)
- Plagued by thousands of water leaks, design flaws, charges of poor execution, use of substandard materials and other issues
- Led to the death of a motorist and criminal arrests when a 24-ton concrete ceiling panel collapsed onto a car

Source: http://www.nbcnews.com/id/22809747/ns/us_newslife/t/million-settlement-covers-big-dig-tragedy/#.XNQs1hRKi70





PROBLEM STATEMENT EXAMPLE: THE "BIG DIG" PROJECT (CONT'D)



- \$407 million in restitution paid by the consortium managing the project
- Several smaller companies agreed to pay a combined sum of approximately
 \$51 million
- * A settlement agreement included a statement of facts as the basis for liability
- The settlement addressed specifically areas of construction management oversight failures:
 - The use of non-specified material
 - The use of substandard materials
 - As well as **ignored observations of** failing epoxy bolt **load tests**
- The issues identified above are typically addressed in construction specifications describing in detail the scope of work, materials, installation, and quality of workmanship

OFFERED SOLUTION



SYSTEMS ENGINEERING AS THE PROFESSIONAL STANDARD OF CARE

- Professional Standard of Care: defined as the systematic exercise of a reasonable level of care, diligence, and skill
- Failure to adhere to the professional standard of care may result in company risk and liability
- In the author's opinion, the Big-Dig issues:
 - Describe a common requirements management and verification & validation challenge
 - Could have been avoided using a structured systems engineering approach

This presentation:

- Describes the application of SE principles to construction specifications in a large infrastructure project using a case study approach
- Presents the application of systems engineering as the systematic exercise of a reasonable level of care
- Demonstrates the Value of Systems Engineering as a liability protection and risk mitigation strategy

PROGRESS



- Problem Statement & Offered Solution
- Background & Introduction
 - Construction Specifications
 - Case Study Project
- Systems Engineering Challenges Faced
- Systems Engineering Objectives
- Systems Engineering Activities Performed
- Summary, Achieved Outcomes & Conclusion

INTRODUCTION CONSTRUCTION SPECIFICATIONS

- Contract documents that govern the construction of building and infrastructure projects (e.g. transportation, water, energy).
- Describe in detail the following requirements:
 - Scope of work,
 - Materials to be used,
 - Installation methods, and
 - Quality of workmanship (including inspection & testing)
- Essential component of the PS&E approach:
 - **P**lans (Drawings),
 - (Construction) <u>Specifications</u>, and
 - (Cost) <u>E</u>stimates.
- Governed by Construction Specifications Institute (CSI)
- CSI MasterFormat Standard: Standardized classification for Construction Specifications.

CSI MASTERFORMAT: 50 DIVISIONS

PROCUREMENT AND CONTRACTING REQUIREMENTS GROUP:

• DIVISION 00 — PROCUREMENT AND CONTRACTING REQUIREMENTS



SPECIFICATIONS GROUP	
GENERAL REQUIREMENTS SUBGRO	FACILITY SERVICES SUBGROUP:
DIVISION 01 — GENERAL REQU	 DIVISION 20 — MECHANICAL SUPPORT
	 DIVISION 21 — FIRE SUPPRESSION
FACILITY CONSTRUCTION SUBGRO	 DIVISION 22 — PLUMBING
DIVISION 02 — EXISTING CONL	DIVISION 23 — HEATING VENTILATING AND AIR CONDITI
DIVISION 03 — CONCRETE	DIVISION 24 — RESERVED FOR FUTURE EXPANSION
DIVISION 04 — MASONRY	 DIVISION 25 — INTEGRATED AUTOMATION
DIVISION 05 — METALS	DIVISION 26 — ELECTRICAL
DIVISION 06 — WOOD, PLASTIC	 DIVISION 27 — COMMUNICATIONS
DIVISION 07 — THERMAL AND	 DIVISION 28 — ELECTRONIC SAFETY AND SECURITY
DIVISION 08 — OPENINGS	
DIVISION 09 — FINISHES	SITE AND INFRASTRUCTURE SUBGROUP:
 DIVISION 10 — SPECIALTIES 	DIVISION 30 — RESERVED FOR FUTURE EXPANSION
 DIVISION 11 — EQUIPMENT 	 DIVISION 31 — EARTHWORK
DIVISION 12 — FURNISHINGS	 DIVISION 32 — EXTERIOR IMPROVEMENTS
DIVISION 13 — SPECIAL CONST	RUC • DIVISION 33 — UTILITIES
DIVISION 14 — CONVEYING EQ	UIPN • DIVISION 34 — TRANSPORTATION
DIVISION 15 — RESERVED FOR	FUTL • DIVISION 35 — WATERWAYS AND MARINE CONSTR
PROCESS EQUIPMENT SUBGROU	JP:
DIVISION 40 — PROCESS INT	ERCONNECTIONS
DIVISION 41 — MATERIAL PR	OCESSING AND HANDLING EQUIPMENT
DIVISION 42 — PROCESS HEA	TING. COOLING. AND DRYING EQUIPMENT

- DIVISION 43 PROCESS GAS AND LIQUID HANDLING, PURIFICATION AND STORAGE EQUIP
- DIVISION 44 POLLUTION CONTROL EQUIPMENT
- DIVISION 45 INDUSTRY-SPECIFIC MANUFACTURING EQUIPMENT
- DIVISION 46 WATER AND WASTEWATER EQUIPMENT
- DIVISION 47 RESERVED FOR FUTURE EXPANSION
 - DIVISION 48 ELECTRICAL POWER GENERATION
- DIVISION 49 RESERVED FOR FUTURE EXPANSION

INTRODUCTION **CONSTRUCTION SPECIFICATIONS**

Part 1 – General: Describes managerial requirements such as applicability, work to be performed, codes and standards, definitions, submittals, quality management, etc.

Part 2 – Products: Describes the (performance) requirements, the acceptable (prescriptive or proprietary) products, materials, and sometimes even specific suppliers. Big-Dig: Would have contained the acceptable materials and material standards.

Part 3 – Execution: Describes the methods of installation and how to measure quality or effectiveness. Big-Dig: Would have identified the **inspections and tests** to be performed, including the bold load tests.

WWW.II

C33, Size No. 57). Deleterio

in ASTM C22

PROCUREMENT AND CONTRACTING REQUIREMENTS GROUP:

DIVISION 00 — PROCUREMENT AND CONTRACTING REQUIREMENTS



accordance with ASTM C31. Cylinders shall be tested in a



C39.







PROGRESS



- Problem Statement & Offered Solution
- Background & Introduction

Systems Engineering Challenges Faced

- Typical Industry Approach to Managing Construction Specifications
 Systems Engineering Challenges
- Systems Engineering Objectives
- Systems Engineering Activities Performed
- Summary, Achieved Outcomes & Conclusion

TYPICAL INDUSTRY APPROACH TO CONSTRUCTION SPECS PROJECT DELIVERY METHODS & SPECIFICATION DEVELOPMENT





TYPICAL INDUSTRY APPROACH TO CONSTRUCTION SPECS CONSTRUCTION QUALITY MANAGEMENT AND PROCEDURES



CQP B1.9 EXCERPT: INSPECTION & TESTING

1.7 QUALITY ASSURANCE/CONTROL

. . .

SPEC: 03 05 15 – PORTLAND CEMENT CONCRETE – QA/QC REQUIREMENTS

D. Contractor's Quality Management Plan shall ensure control and uniformity of materials, conformance with accepted mix designs, and prompt and proper delivery of concrete to the jobsite in accordance with applicable requirements of ASTM C94. Include in the plan all tests the Contractor will perform to verify compliance with Specification requirements, and the independent laboratory the Contractor intendet to engage to perform the tests.

CQP No.	CONSTRUCTION QUALITY PROCEDURES (CQP)	Revision Number	Revision or Issue Date
B1.1	Daily Inspection Reporting	2	03/30/16
B1.2	Materials Receiving Inspection and Acceptance	2	03/30/16
B1.3	Pre-Activity Meeting	2	03/30/16
B1.4	Control of Measuring and Test Equipment	2	03/30/16
B1.5	Material Storage, Identification and Traceability	2	03/30/16
B1.6	Material sampling and Testing	2	03/30/16
B1.7	Off-Site Inspection	2	03/30/16
B1.8	Management of Construction Subcontractors	2	03/30/16
B1.9	Inspection and Testing	2	03/30/16
B1.10	Request For Information	2	03/30/16
B1.11	Quality Hold Points	2	03/30/16
B1.12	Field Change Notice	2	03/30/16
B1.13	Quality Assurance Audit of Construction Activities	2	03/30/16
B1.14	Construction Surveying	2	03/30/16
B1.15	Construction Submittal Workflow Process	2	03/30/16

Receiving Material Inspection and Testing

- Incoming material or equipment shall be identified, inspected, and tested as required by applicable ITPs and CQP B1.2, Materials Receiving, Inspection, and Acceptance.
- Material or equipment manufactured in factories (systems components and equipment) will be subject to factory acceptance tests in accordance with the factory test items list and factory test schedule agreed between TPZP and vendors, as defined in CQP-B1.7, Off-site Inspection. Upon arrival to the project site storage facility, material and/or equipment will be checked visually against shipment documents to verify damage or short quantities.
- Incoming material or equipment will not be used until the required inspection and tests are completed or the necessary inspection and test reports are received and verified.
- Material or services not conforming to specified requirements will be identified and subsequent corrective action will be treated in accordance with CQP B1.2, Materials Receiving, Inspection, and Acceptance.

In-process Inspection and Testing

 During construction, inspection and testing will be carried out in accordance with the requirements of the ITP and Quality Inspection Schedule. Various elements will be checked for compliance with the Technical Contract Requirements established in DOORS. The requirements for each specific activity will be filtered and exported on an RVTM hard/electronic copy in Microsoft Word, Excel, and Adobe PDF format that will be verified by the inspection staff providing objective evidence that inspection and test plans and

procedures meet Technical Contrac provided (see Form CQP B1.9FB).



 Works subject to the requirements of and tests are completed or necessary reports

nated inspections

A template is

and tests are completed or necessary reports are received and verified.

The inspection and tests specified in the ITP will be confirmed with the signature of the nominated personnel upon completion of the operation and prior to commencement of the next operation.

- Inspection checklists could be developed for certain activities. Checklists will show that the concerned parties have checked the required points.
- Non-conformances identified during an in-process inspection will be handled and recorded in accordance with CQP B1.2 - Materials Receiving, Inspection, and Acceptance.

Final Inspection and Testing. I inal inspection and testing shall take place as required by the Contract. This will include the review of inspection records to verify that the product or service has been inspected

TYPICAL INDUSTRY APPROACH TO CONSTRUCTION SPECS CONSTRUCTION QUALITY FORMS



			_								
		SECTION 03 05 15 PORTLAND CEMENT CONCRETE						C PLAC	QP B1.9 EMENT C	FORM D: CON HECKLIST (PO	ICRETE UR CARD)
PART	1 - GENERAL		CON	ICRETE PLACEM	ENT CI	HECKLIS	T (POU	R CAF	RD)		
1.6 A.	SUBMITTALS Concrete Mix Design	s: Submit mix designs as herein specifie	Note: Constru a Hold F	Once, it has been determined t oction Superintendent or design Point Release Report and kept v	hat the wor ee and the vith the qua	k meets the pro TPZP QC Inspec ality records on	oject requiem tor will sign t Sharepoint.	ents and a his Pour Ca	II relevant ard allowin	items below h ng concrete pla	ave been ac cement to a
	minimum of 30 days prior to batching or delivering concrete.		Contractor: Da				Date:				
B.	B. Product Data: Submit manufacturer's product data for propos			Milestone:				Structu	re Түре:		
C. Aggregate Source: Submit aggregate source.				t Documents Used For tion:							
PART	2 - PRODUCTS										
			ltem #	Description		Verified	Production	ata	N/A	Accented	QC
2.3 A	MIX DESIGNS	portions shall conform to the applicat	1	Access/Work Plans: Reviewed and approved		vernied		ale	Inicials	Accepted	Iniciais
	A. Selection of mix proportions than conform to the applica ACI 211.2. Concrete shall comply with ACI 301 and ACI designs will produce concrete suited for proper placement		2	Layout: Horizontal & vertical contro	ol verifed.						\square
B.	mixes shall include re Mix design for subwa	ecommended amounts of admixture and ay structures and below-grade retaining v	3	Concrete Mix Design: Submitted a for use	nd approved	APPROVE SUBMITTA	D L				
	shall include 15 percent replacement of the cement with admixture conforming to ASTM C1017, to provide a den		4	Specifications: Confirmation of the agency specifications	governing						
C.	shrinkage and permea Mix design for archi	ability characteristics. tectural concrete and formed concrete th	5	Layout: Checked for compliance wi details	th plans and						
0.	the finished work sh along with a plastic	all include a minimum 10 percent replace	ment of C1017	the cement with fly ash, SYM to provide a dense and	p2021						

TYPICAL INDUSTRY APPROACH TO CONSTRUCTION SPECS INSPECTION & TESTING PLANS (ITP)



		SECTION 02 05 15	4.2.4	Concrete Com	nling and Tax	tin a	PRODUCTION D	ILLED CONCRETE SHAFT	
		SECTION 03 03 13	4.2.1	Concrete Sam	ping and res	sung –			
		PORTLAND CEMENT CONCRETE		[Source: Specif	ications Section	on <mark>03 05</mark> 15	 Portland Cem 	ent Concrete, Section 3	3.1]
PAR	T 3 - EXECUTION	INSPECTION		Test	Test Method	Sample Size	Sampling Location	QC Test Frequency	QA Test Frequency
3.1 B.	FIELD QUALITY (Methods of Sampling at	CONTROL & TESTING nd Testing:		Slump	ASTM C143	See test method	Concrete truck discharge chute	One test per each 50 CY of concrete delivered	One at FAI, or as determined by CQAM
	2. Slump Tests: The slump tests of co C143. At least or concrete delivere	ble shall be obtained from a different batch of the above-specified Contractor employed test oncrete during placing of concrete, as require the test shall be performed at the delivery true ed.	of st e	Uniformity	ASTM C94, Annex A1	See test method	Concrete truck discharge chute	Each batch of concrete	One at FAI, or as determined by CQAM
	 Tests for Concrete uniformity in acc tested as specifie Tests for Concrete ambient temperate compression test herein for hot and Strength Tests: a. Prepare, can laboratory accordance 	te Uniformity: The same testing laboratory s cordance with ASTM C94, Annex A1. Ea d in ASTM C94, Annex A1 ete Temperature: Freshly mixed concrete sh ature is below 40 degrees F and above 8 c cylinders are made. The concrete temper c cylinders made. Refer to Article entitled " d cold weather remedial requirements. ast, and deliver to the same independent te cured compression test samples. Cylinder e with ASTM C31. Cylinders shall be test	Temperature				Test hourly when concrete temp is below 40 degrees F and above 80 degrees F, and each time compression test cylinders are made.	One at FAI, or as determined by CQAM	
	C39.			Compressive Strength	ASTM C31 ASTM C39	See test method	Concrete truck discharge	Four cylinders for each 100 cubic vards or fraction	One at FAI, or as determined by CQAM

TYPICAL INDUSTRY APPROACH TO CONSTRUCTION SPECS QUALITY RECORDS

D



TYPICAL INDUSTRY APPROACH TO CONSTRUCTION SPECS Additional CHSRS Verification & Validation Requirements



Doc. ID	Document Section	Requirements Specification Assigned to Avenue 11 Overhead		Allocation	Quality Record	Reference Folder		
Portland Cement Concrete 03 05 15	3.1B.1 Field Quality Control	Sampling: Representative composite samples shall be taken in accordance with ASTM C172. Each sample shall be obtained from a different batch of concrete on a random basis.	4	CIDH Abutment Retaining Walls Wing Walls Deck	QR-CON2	8.1 Construction Quality Records https:// egnyte.com/Sin 200A QC NCRs/7.01%20-%20Mil 200H/8.0%20Quality/8.1%20Cons		
Portland Cement Concrete 03 05 15	3.1B.2 Field Quality Control	Slump Tests: ACI-certified personnel shall perform slump tests of concrete during placing of concrete, as required, in accordance with ASTM C143. At least one test shall be performed at the delivery trucks for each 100 cubic yards of concrete delivered		CIDH Abutment Retaining Walls Wing Walls Deck	QR-CON2 REFERENCE EVIDENC	8.1 Construction Quality Records S & TRACES TO OBJECTIVE CE (QUALITY RECORDS)		
Portland Cement Concrete 03 05 15	3.1B.3 Field Quality Control	Tests for Concrete Uniformity: The same testing laboratory shall perform tests for concrete uniformity in accordance with ASTM C94, Annex A1. Each batch of concrete shall be tested as specified in ASTM C94, Annex A1	1	CIDH Abutment Retaining Walls Wing Walls Deck	QR-CON2	8.1 Construction Quality Records https:// egnyte.com/Sin 200A QC NCRs/7.01%20-%20Mil 200H/8.0%20Quality/8.1%20Cons		
Portland Cement Concrete 03 05 15	3.1B.4 Field Quality Control	Tests for Concrete Temperature: Freshly mixed concrete shall be tested hourly when the ambient temperature is below 40 degrees F and above 80 degrees F, and each time compression test cylinders are made. The concrete temperature shall be recorded on all compression test cylinders.	1	CIDH Abutment Retaining Walls Wing Walls Deck	QR-CON2	8.1 Construction Quality Records https:// egnyte.com/Sin 20QA_QC_NCRs/7.01%20-%20Mil 20OH/8.0%20Quality/8.1%20Cons		
Portland Cement Concrete 03 05 15	3.1B.5 Field Quality Control	Strength Tests: a. Prepare, cast, and deliver to the same independent testing laboratory, cylinders for laboratory-cured compression test samples. Cylinders shall be made and cured in accordance with ASTM C31.	C	CIDH Abutment Retaining Walls Wing Walls	QR-CON3	8.1 Construction Quality Records https:// egnyte.com/Sin 200A QC NCRs/7.01%20-%20Mil 200H/8.0%20Quality/8.1%20Cons		
		Cylinders shall be tested in accordance with ASTM C39.		REQUIREMENTS VERIFICATION TRACEABILITY MATRIX (RVTM)				

www.incose.org/symp2021

PROGRESS



- Problem Statement & Offered Solution
- Background & Introduction
- Systems Engineering Challenges Faced
 - Typical Industry Approach to Managing Construction Specifications
 - Systems Engineering Challenges
- Systems Engineering Objectives
- Systems Engineering Activities Performed
- Summary, Achieved Outcomes & Conclusion

SYSTEMS ENGINEERING CHALLENGES OVERVIEW



Selected Challenges:

- Large Number of Contract Documents and Requirements
- Specification and Requirements Applicability
- Different Implementation by each Contractor
- Submittal Fragmentation and Submittal Log
- Availability of Construction Phase Submittals
- Organization of Quality Records
- Traceability to Objective Evidence

SYSTEMS ENGINEERING CHALLENGES LARGE # OF CONTRACT REQUIREMENTS, SPEC & REQ. APPLICABILITY



1		л Г
	CONSTRUCTION PACKAGE 1 (HSR 13-06)	D1 02 02
GENERAL PROVISIO	ONS DAGREEMENT: HSR 13-06	02 02 02 02
34 Pages, 1,334 <i>Shall</i> St	TATEMENTS Pt A - Subpart 1 – Signature Document	02
	 B2 - Pt A - Subpart 2 – Special Provisions 	D1 03
	B2 - Pt B – General Provisions	03
	 B2 - Pt C - Subpart 1 – Scope of Work 	03
	 B2 - Pt D - Subpart 1 – Community Benefits Agreement 	03
SCOPE OF WORK	3 - Pt A - Subpart 1 – Basis of Design	03
7 DAOFO 447 SUALL STAT	3 - Pt A - Subpart 2 – Organizational Conflict of Interest Policy	03
FAGES, 447 SHALL STAT	EIVENTS IS - FLA - Subpart 3 - Revised Small and Disadvantaged Business Enterprise Program	03
	B3 - Pt B - Subpart 2 - Reliability Availability and Maintainability	0.
	P2 Pt B - Subpart 5 – Design Variance Request Process	0
	A NULAL T B - Subpart 6 - Safety and Security Management Plan	0
DESIGN CRITERIA IVI	ANUAL t B - Subpart 7 – Aesthetic Guidelines for Non-Station Structures	0.
279 Pages, 7,951 <i>Shall</i> 3	STATEMENTS I B - Subpart 8 – Cost and Scheduling Controls Program	D
	B3 - H B - Subpart 9 – Payment Milestone Data Pack Specifications	0
	 B3 - Pt C - Subpart 1 – Design Criteria 	0
	 B3 - Pt C - Suppart 2 – CADD Manual 	0
	B3 - Pt C - Subpart 3 – Plan Preparation Manual	D 01
	 B3 - Pt D - Subpart 1 – Third Party Entities Master and Cooperative Agreement Updates 	0
	 B3 - Pt D - Subpart 2 – Approach for Obtaining ICS Environmental Approvals/Permits B4 D - Subpart 4 – Millionica Mediation and Basedian Basedian 	
THIRD PARTY AGREE	MENTS Pt D - Subpart 4 – Mitigation, Monitoring and Reporting Program	
1 PAGES 1 819 SHALL ST	TATEMENTS Pt D - Subpart 6 - CP01 Transportation Mitigation	
TTAGES, 1,019 ONALL O	Pt D - Subpart 7 – Draft Engineering and Construction LIPRR Agreement	
	 B3 - Pt D - Subpart 7 – Caltrans and Railroad Agreements Caltrans SR99 	
	 B3 - Pt D - Subpart 8 – City Fresno Design Guidelines Clarifications 	
	Pt E - Subpart 1 – Directive Drawings	
STANDARD SPECIFICA	ATIONS Pt E - Subpart 2 – Preliminary Ground Motion Data	
4 PAGES. 2.274 SHALL ST	FATEMENTS Pt E - Subpart 3 – Record of Survey and Control Monument Data	
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Pt E - Subpart 4 – Right-of-Way Acquisition Plan	
	 B3 - Pt E - Subpart 5 – Geotechnical Baseline Re Which of the 1 000s of 	Requ
	American Avenue	nequ
	• B3 - PTE - Subpart 5 – Geotechnical Baseline Re apply to Ave 10 C	verhe
	Environmental Decumenta	
	Environmental Documents	

Table of Contents

DIVISION 02 -	 TECHNICAL GENERAL REQUIREMENTS AND EXI 	STING CONDITIONS	S
02 01 00	STANDARD SPECIFICATIONS GENERAL STATE	EMENTS	
02 01 56.39	TEMPORARY TREE AND PLANT PROTECTION		
02 21 13	SITE SURVEYS		FINISHES
02 21 23	FIELD ENGINEERING	00.06.00	
02 21 33	PHOTOGRAPHIC DOCUMENTATION	09 90 00	HIGH-PERIORMANCE COATINGS
02 22 00	EXISTING CONDITIONS ASSESSMENT		
02 41 00	DEMOLITION	DIVISION 31 – I	EARTHWORK
		31 05 00	COMMON WORK RESULTS FOR EARTHWORK
DIVISION 03 -	- CONCRETE	31 09 13	GEOTECHNICAL INSTRUMENTATION AND MONITORING
03 05 15	PORTLAND CEMENT CONCRETE	31 11 00	CLEARING AND GRUBBING
03 05 18	PRESTRESSED CONCRETE	31 23 19	DEWATERING
03 11 00	CONCRETE FORMING	31 23 26	AGGREGATE DRAINAGE LAYER
03 11 14	FALSEWORK	31 35 00	SLOPE PROTECTION
03 15 00	CONCRETE ACCESSORIES	31 35 33	
03 15 13	WATERSTOPS	21 20 12	
03 15 15	ELASTOMERIC BEARING PADS	51 30 13	REINFORCED SLOPES AND EARTH STRUCTURES
03 15 23	CONCRETE DEINEODCINC	31 39 13	GROUND ANCHORS
03 20 00	CONCRETE REINFORCING	31 50 13	TEMPORARY EXCAVATION SUPPORT AND PROTECTION
03 30 00	CAST-IN-PLACE CONCRETE	31 62 00	DRIVEN PILES
03 35 00	SHOTCDETE	31 63 29	DRILLED CONCRETE PIERS AND SHAFTS
03 40 00			
03 43 00	PRECAST CONCRETE SEGMENTAL CONSTRUCT	DIVISION 32 - I	EXTERIOR IMPROVEMENTS
03 62 00	NON-SHPINK GPOLITING	32 11 23	AGGREGATE BASE COURSES
03 70 00	MASS CONCRETE	32 31 13	CHAIN LINK FENCES AND GATES
	The concrete	32 90 00	PLANTING
DIVISION 05 -	– METAL	52 50 00	Barrino
05 05 22	METAL WELDING		
05 12 00	STRUCTURAL STEEL FRAMING		
05 50 00	METAL FABRICATIONS	33 05 16	
05 51 00	METAL STAIRS	33 05 25	SUPPORT AND PROTECTION OF UTILITIES
		33 05 28	TRENCHING AND BACKFILLING FOR UTILITIES
DIVISION 07 -	- THERMAL AND MOISTURE PROTECTION	33 05 33	RELOCATION OF EXISTING UTILITIES
07 95 63	BRIDGE E		
07 95 66 07 95 73	BRIDGE E TUNNEL !		
quirem	nents		1.
head?			

SYSTEMS ENGINEERING CHALLENGES CONSTRUCTION PHASE SUBMITTALS & SUBMITTAL LOG



Construction Phase submittals are those submittals that are required by the Construction Specifications and do not require submittal to the Authority unless otherwise stated in the Contract. The Contractor shall provide access to the Authority for the review and audit of these submittals. The Contractor shall provide copies of these states in the request.

SECTION 03 05 15

PORTLAND CEMENT CONCRETE

PART 1 - GENERAL

В.

1.6 SUBMITTALS

A. Concrete Mix Designs: Submit mix designs as herein specified in Article entitled "Mix Designs". Include laboratory test reports of trial strength and shrinkage tests. Submit mix designs a minimum of 30 days prior to batching or delivering concrete.

Product Data: Submit manufacturer's product data for proposed con

Which Concrete Mix Design(s) apply to Ave 10 Overhead?

15362

15063

14675

14371

13729

13480

12987

12970

12281

11363

10919

10918

10917

10916

- C. Aggregate Source: Submit aggregate source.
- D. Affidavits/Certificates: For each shipment of materials, submit evidence of compliance with Specification requirements for cement, aggregate, supplementary cementitious materials, and admixtures. Mill tests and manufacturers' certification of compliance with ASTM Specifications may be accepted in lieu of testing of cement and analysis of aggregates. Certificates of Compliance shall be signed by the materials manufacturer and the Contractor.
- E. Batch Tickets: Submit a delivery ticket with each batch of concrete delivered to the site in mp accordance with the requirements of ASTM C94.

(00	SUBMITTAL LOG		
		Title	SubmittalType	LatestReviewCy
		4000psi Concrete Mix Dsgn 53T1G01C	INFO	000
		4000ps Concrete Mix Design 60T1G01	INFO	000
		Project Wide 5000 ps Concrete Mix	INFO	000
		Road 27 OH- 8500psi Concrete Mix	INFO	000
		OM 5000 ps Concrete Mix #60F1G03B	INFO	000
		PW- Concrete Mix Design #73T1G05F	INFO	001
		UPRR Concrete Mix Osgn for NON-UPRR	INFO	000
		SR180 5000ps Concrete Mix Design	INFO	000
		UPRR 4000ps Concrete Mix Design	INFO	000
		COF- Asphalt Concrete Mix Design	INFO	000
		Project Wide-CIDH Concrete Mix Dsgn	INFO	000
		Project Wide CIDH Concrete Mix Dsgn	APPROVAL	000
l		Tuolumne OH - MSE Wal Concrete Mix	INFO	000
l		Tuolumne OH-MSE Wall Concrete Mix	INFO	000
		Project Wide 6000 ps Concrete Mix	INFO	000
		5000psi Concrete Mix Dsgn 50B1G03	INFO	000
		6000ps Concrete Mix Design 50F1G12	INFO	000
		6000 psi Concrete Mix Design	INFO	000
		4000 PSI Concrete Mix 40F1G03	INFO	99B
		5000psi Concrete Mix Design 50F1G03	INFO	000

SYSTEMS ENGINEERING CHALLENGES TRACING, LOCATING, AND VERIFYING TO OBJECTIVE EVIDENCE



Doc. ID	Document Section	Requirements Sp	ecification Assigned to Avenue 11 Over	head	Allocation	Quality Record	Reference Folder
Portland Cement Concrete 03 05 15	3.1B.2 Field Quality Control	Slump Tests concrete dur ASTM C143. trucks for ea	ACI-certified personnel shall per ing placing of concrete, as requ At least one test shall be perfor och 100 cubic yards of concrete d	erform slump tests of ired, in accordance with rmed at the delivery elivered	CIDH Abutment Retaining W Wing Walls Deck	QR-CON2 DBJECTIVE EVIDENCE	8.1 Construction Quality Records https://egnyte.com/Sin 20QA_QC_NCRs/7.01%20-%20Mil 20OH/8.0%20Quality/8.1%20Cons
1.0 Executive	Summary QUALIT	Y MILESTONE ACK (QMDP)	8.1 Construction Quality Records	1,250+ Quality R	ecords?	6 Files Tutor Perini 💋 ZACH	RY PARSONS, A Joint Venture
3.0 Verificatio	n, Validation, and Sel	f Certificatio	CC-REBR-STR07-110617_Ave_1	1_Abut_1_2_CIDH_Piles_Rebar	r_MRIR.pdf Subcor Prime Contra Job Name &	tractor's Daily Repo	DUE by 9AM following day Subcontractors: Moore Twining Assoc. Inc. CP1 Date: //-//-/- Workbox 2004/10000000000000000000000000000000000
4.0 Third Party	y Requirements		CC STR07-Drilled Shaft C	ertificate of Conformance Abut	ard.pdf	of Work and Location: STR OF	7 1112 2329 Compactilu 7 1112 2344 Conc. Sample
5.0 Milestones	s Photographic Evide	nce	CL-CON1-STR07-111517_Ave_	11_Abut_1_2_CIDH_Piles_Dour_	_Card.pdf	Contractor's Daily R Contractor: <u>Tutor Perini/Zachry/Perini</u> me & Aree: <u>California High Speed</u>	eport DUE by 9AM following day arsons_JV Subcontractors: Moore Twining Assoc. Inc. Rail_CP1 Date: /////// ///
7.0 Disposition	n of Comments		PDF CL-GBO1-STR07-032619_AVE_	11_Grounding_Bonding_QC_Ch /et_Hole_Drilled_Shaft_Concret	te_MD_Stamped	n: <u>Acc. II OH MADERA</u> ption of Work and Location: <u>/</u> / / F: Please indicate, by category, the n	TR 232 9 STR Q1 COMPACTION TR 232 9 STR Q1 COMPACTION TR 2344 STR Q7 COMPACTION TR 2344 STR Q7 COMPACTION umber of workers on site, and the hours, for the above date.
8.0 Quality			PDF QR-CON2-STR07-111417_ITR2	344_Abut_1_CIDH_Pile_PCC_D	UIR_35691_1.pdf	ATEGORY # HOURS erintendents Corers S erent Finishers I penters 4 k Drivers I mbers Tot	CATEGORY # Prous Electricians Diperating Eng. 1 & Electricians Unreyors aniners Carpenters at Work Force:
9.0 Drawings,	Documents, and Rec	ords	QR-CON2-	344_CIDH_Piles_PCC_DIR_357	64_1.pdf	es / Accidents/ Incidents (circle or Make / Model Equipment # /	Overs Aspitable NO Overs Aspitable Incense Plate GAS DIESEL Hour Meter / Mileage (Finish) Covers Aspitable 2 (Og 20/2)

Systems Engineering Challenges Summary











PROGRESS



- Problem Statement & Offered Solution
- Background & Introduction
- Systems Engineering Challenges Faced

Systems Engineering Objectives

- Objectives
- Constraints & Considerations
- Envisioned Solution
- Systems Engineering Activities Performed
- Summary, Achieved Outcomes & Conclusion

Systems Engineering Objectives Objectives



- 1. Address the Systems Engineering Challenges described above
 - Determine governing construction specifications and requirements
 - Analyze and allocate applicable requirements to individual HSR milestones and HSR milestone elements (e.g. foundations, columns, deck, etc.)
 - Create a structured quality record storage system suitable for the large amount of records
 - Provide effective traceability between requirements and objective evidence
- 2. Demonstrate the Professional Standard of Care
 - Systematically exercise a reasonable level of care, diligence, and skill
- 3. Avoid the cautionary tale of the Big-Dig scenario
 - Provide a requirement-based approach demonstrating the correct use of specified materials and the successful execution of all specified inspections and tests

4. Deliver the successful HSR milestones Acceptance and Certification

- Handed over / input into the next HSR track and systems contractor

SYSTEMS ENGINEERING OBJECTIVES CONSTRAINTS & CONSIDERATIONS



- 1. Construction Industry
 - Used to plans, specifications, and estimates (PS&E) approach, CSI MasterFormat
 - Average annual gross domestic product (GDP) of more than \$636B, 7.2 million employees
 - Consider continued use of the construction specifications

2. Quality Management vs. Systems Engineering

- Systems engineering (incl. Verification & Validation) widely unknown in construction industry
- Consider integration of the quality management system including plans, procedures, forms, inspection and test plans and procedures, and resulting quality records

3. Contract Management

- Any change to an executed contract has the potential to result in contractor claims
- Consider re-use of construction specifications, quality documents, submittal log, ITPs, QMDP, etc.

4. Contractor Deliverables

- Consider re-using existing specifications, requirements analysis, breakdown structures, etc.

5. Human Aspect

- Consider resistance to change, adding value through improved, more effective / efficient processes

SYSTEMS ENGINEERING OBJECTIVES Envisioned Solution: Four (4) Step Approach





PROGRESS



- Problem Statement & Offered Solution
- Background & Introduction
- Systems Engineering Challenges Faced
- Systems Engineering Objectives

Systems Engineering Activities Performed

- 1. Requirements Management
- 2. System Breakdown Structure
- 3. Verification and Validation
- 4. Traceability

Summary, Achieved Outcomes & Conclusion

SYSTEMS ENGINEERING ACTIVITIES PERFORMED STEP 1: REQUIREMENTS MANAGEMENT – REQ. MGMT. DATABASE MODEL



SYSTEMS ENGINEERING ACTIVITIES PERFORMED STEP 1: REQUIREMENTS MANAGEMENT – ANALYSIS & ALLOCATION





SYSTEMS ENGINEERING ACTIVITIES PERFORMED STEP 1: REQUIREMENTS MANAGEMENT – APPLICABLE SPECIFICATIONS



California High-Speed Train Project

Construction Package 1



INSPECTION AND TEST PLAN FOR PRODUCTION DRILLED CONCRETE SHAFT

Revision 1

July, 2016



Prepared by:

1.2 Reference Documents

The referenced documents are considered mandatory as determined applicable by TPZP and for those sections or portion thereof identified in this ITP. The list may be updated to conform to the CP 1 Project Construction Specifications.

- CHSTP Standard Specifications, Executed Version, Rev 1 July 12, 2013
- General Provisions, Executed Version, Rev 7 July 30, 2013
- Scope of Work, Executed Version, Rev 9 July 31, 2013
- CP 1 Construction Specifications Ready for Construction (RFC), Volume 1
 - o 03 05 15 Portland Cement Concrete
 - 03 11 00 Concrete Forming
 - o 03 20 00 Concrete Reinforcing
 - o 03 30 00 Cast-In-Place Concrete

6 CONSTRUCTION SPECS APPLICABLE TO CIDHS

- 26 05 26 Grounding and Bonding
- Approved RFC or Early Start of Construction (ESOC) Plans

31 63 29 - Drilled Concrete Piers and Shafts

• Approved Shop Drawings

0

- Quality Management Plan (QMP), Rev 1 April, 2016
- 2010 Standard Specifications & Special Amendments State of California

cose.org/symp2021



SYSTEMS ENGINEERING ACTIVITIES PERFORMED STEP 2: SYSTEM BREAKDOWN STRUCTURE (SBS)



Table 1 - RAM Allocation Matrix

CP1 RAM ALLOCATION REPORT (RAR)

10

		Work E	lements (A	ttachment 4 -Sc	ope Elements										ALLOCATI		R
				Matrix)					RAM Attribute	s							
Item	RAM ID #	Discipline	Category	Item	Major category	Element	Lowest Level Replacement Unit	Design Life/Reliability	Maintainability	Accessibility	Maintenanc e Window	MTTR (5 hours window or not)	Discipline Allocation	Subcontrac tor/Suppli er Name	Subcontractor/ Supplier Cut Sheet/Product Data	Historical Data/Similar Element Reference	
18	RAM 18	Site Work	Structures	Grade Separations (HST overpass and underpass)		Substructure	Reinforced concrete bridge rail	100 years	Yes, from the bridge deck.	This is always accessible from top of the bridge.	Between 12:01 am and 05:00 am daily	Less than 5 hours	Structures	TBD	TBD	TBD	
19	RAM 19	Site Work	Structures	Grade Separations (HST overpass and underpass)		Substructure	010 St	100 years	Yes, from the	This is always accessible from the bridge deck.	Between 12:01 am and 05:00 am daily	Less than 5 hours	Structures	TBD	TBD	TBD	
20	RAM 20	Site Work	Structures	Grade Separations (HST overpass and underpass)		Substructure	020_Su	iperstruc	ture	This is always accessible from underneath by boom trucks, ladders, etc.	Between 12:01 am and 05:00 am daily	Less than 5 hours	Structures	TBD	TBD	TBD	
21	RAM 21	Site Work	Structures	Grade Separations (HST overpass and underpass)		Substructure	030_SU	arings	re	This is always accessible from underneath by boo ladd	Between 12:01 am and 05:00	Less than 5 hours	Structures	TBD	тво	тво	
22	RAM 22	Site Work	Structures	Grade Separations (HST overpass and underpass)		Substructure	050_Ex	pansion <u>.</u> blystyren	_Joints e	This acce und boo ladd	22_Rein	forced	l_Conci	rete_Ab	outments	8D	
23	RAM 23	Site Work	Structures	Grade Separations (HST overpass and underpass)		Substructure	070_Ut 080_Lig	tilities ghting		This acce is bu Exca how elen	23_Rein 24_Rein 25_CIDF	forcec forcec	l_Conci l_Conci	rete_Pil rete_Pil	e_Caps er_Caps	3D	
										des "capacity protected" to mitigate accessibility needs.							
²⁴	AM II	Site Work	Structures	Grade Separations (HST overpass and underpass)		Substructure	Reinforced concrete pier caps	100 years	Yee, from adjacent ground.	This is always accessible from underneath by boom trucks, ladders, etc.	Between 12:01 am and 05:00 am daily	Less than 5 hours	Structures	TBD	TBD	TBD	
25	RAM 25	Site Work	Structures	Grade Separations (HST overpass and underpass)	Elemen	Substructure	CIDH	100 years	No	This is buried and essentially inaccessible. Element is designed as	N/A	N/A	Structures	TBD	TBD	TBD	3

SYSTEMS ENGINEERING ACTIVITIES PERFORMED STEP 2: USING SBS FOR REQUIREMENTS ALLOCATION



 3.1.8.5 Field Quality Control S Strength Tests: a. Prepare, cast, and deliver to the same independent testing laboratory, cylinders for laboratory-cured compression test samples. Cylinders shall be made and cured in accordance with ASTM C31. Cylinders shall be tested in accordance with ASTM C39. b. The minimum number of test cylinders to be made for each class of concrete and for each placement shall be four cylinders for each 300 cubic yards or fraction thereof. When ad and 28-day tests, c. All cylinders in this number on the Contractor's inder d. From each set cylinders at 28 day satisfactory, the field. Oto_Superstructure i. The event the of 040_Bearings i. The event the of 050_Expansion_Joints 	Document Section	Requirements Text			Sub Allocation #1	Sub Allocation #2
Laboratory shall t e acc_aptation_concrete_forced_concrete_Abutments 03_30_00-CIP 03 05 15 - PORTLAND 070_Utilities 23_Reinforced_Concrete_Pile_Caps 03_35_00-CF 080_Lighting 24_Reinforced_Concrete_Pile_Caps 26_05_26-G&B 125_CIDH 31_63_29-DCP&S	3.1.B.5 Field Quality Control 03 05 15 – PO CEMENT CONCRE	 Strength Tests: a. Prepare, cast, all for laboratory-cure accordance with ASASTM C39. b. The minimum multiple for each placement thereof. When ad and 28-day tests, respectively. c. All cylinders in this number on th Contractor's inder d. From each set cylinders at 28 da satisfactory, the fle. In the event the Laboratory shall t engineer. DRTLAND ETE (PCC) 	nd deliver to the same independent d compression test samples. Cylind STM C31. Cylinders shall be tested umber of test cylinders for each 30 SYSTEM ELEMENTS a minimum 010_Structure_Wide 020_Superstructure 030_Substructure 040_Bearings 050_Expansion_Joints 060_Polystyrene 070_Utilities 080_Lighting	testing laboratory, cylinders lers shall be made and cured in in accordance with for each class of concrete and 0 cubic yards or fraction uired beyond the normal 7- of two test cylinders. number on one end. Record ders shall be cured by the LLRUS 7 days and two ests are 21_Reinforced_Concrete 22_Reinforced_Concrete 23_Reinforced_Concrete 24_Reinforced_Concrete 25_CIDH	010_Structure_Wide 020_Superstructure 030_Substructure e_Columns e_Abutments e_Pile_Caps e_Pier_Caps	00_Structure_Wide_Document 17_Reinforced_Concrete 18_Reinforced_concrete_bridge_rail 20_Prestressed_concrete_beams 21_Reinforced_concrete_abutments 23_Reinforced_concrete_pile_caps 24_Reinforced_concrete_pier_caps 25_CIDH SPECIFICATIONS 03_05_15-PCC 03_20_00-CR 03_30_00-CIP 03_35_00-CF 26_05_26-G&B 31_63_29-DCP&S



SYSTEMS ENGINEERING ACTIVITIES PERFORMED STEP 3: VERIFICATION & VALIDATION – LOCATING THE QUALITY RECORDS



03 05 15 Portland Cement Concrete DL - 191 Executed	/	1.6 SLIP-A-Concrete Mix Designs pdf		
1 GENERAL	/	1.6 SUB-B-Product Data.pdf	Connection Man Devices	CONCRETE MIX DESIGN
1.6 SUBMITTALS		1.6_SUB-C-Aggregate_Source.pdf	Concrete Mix Design 5 over 7/6/16 PHOJECT: California High Speed R II - CPT-	orte CONDENSATE: Enclanding californing der processes, mann, indimisers, eines and gronolikere in benählteten and
A.Concrete Mix Designs: Submit mix	designs as herein specified in Article entitled "Mix	1.6_SUB-D-Certificates.pdf	USE Drilled Shafts: Wet Hole Mixtesion	debaits calculations, analysis, local institutions, or machinelis exveloped in accessible institution and increases in a debandation and advances wanted by in field of angress, construction design charges or design network/markets.
Include laboratory test reports of tria	al strength and shrinkage tests. Submit mix design	1.6_SUB-E-Batch_Tickets.pdf	AGG 1: 1* x M Gravel AGG 2: 3/8* x #8 Pea Gravel AGG 3: Concernite Sand CHE	USYDFras bartynowed M28-OOM/056 LEND: Dr. Y & Alleren (XXARS) EDMMA (1994) Stream (XXARS)
minimum of 30 days prior to batchin	⁹ 🗸 📙 8.0 Quality	1.7 QAC-A-Qualitied Concrete Supplier.pdf	SIEVE AGS 1: AGS 2: Bré SIZE, mm BRADING GRADING C 1 1.22 100 100 MS4 11 00 100	
2 PRODUCTS	✓	1.7 OAC-B-Concrete Supplier.pdf	3/41 80 100 Sign 1/21 3/87 2.1 MAT - A - Portland Co	100 SURV [X]
2.1 MATERIALS	> 010 Structure Wide	1.7_QAC-C-Mix_Designs.pdf	24 #8 #16 #30	
A. Portland Cement: ASTM C150, Ty		1.7_QAC-D-Contractor's_Quality_Management_	e50 #100 #200	PORTLAND CEMENT
where high early strength concrete i		1.7_QAC-E-Cement_and_Aggregates.pdf	MATERIAL CEMENT:	CEMENT TEST REPORT
3 EXECUTION	21 Painforred Concrete Columns	🐕 1.8_ENV-A-Hot_Weather_Concreting.pdf	GGBF Slag: (mpk AGG 1: 11 x) AGG 2: 318': STAND	te Type II/V, Low Alkali; ASTM C 150-36 maneta August 202 ABR CHTMACAL RECOMPRATING
3.1 FIELD QUALITY CONTROL		1.8_ENV-B-Cold_Weather_Concreting.pdf	AGG 3: Cons AIR: billoon Dioxide (NOU), WATER: Aluminum Childe (ADC	ASTM C 114 RESULTS TYPE II TYPE V 5 72.6
B. Methods of San pling and Testing	> 22_Reinforced_Concrete_Abutmen	2.1_MAT-A-Portland_Cement.pdf	TOTALS: Former (Galaction Statemer)	3.1 FQC B.5 Methods of Sampling & Testing . (
1. Sampling: Representative compos	it > _ 23_Reinforced_Concrete_Pile_Caps	2.1 MAT-B-Aggregates.pdf	DESIGN STRENC 4000 psi at 28-ck AGGREGATES: AS Aliaites (Na20 epitrali	FIELD QUALITY CONTROL:
S. Strength Tests:	A 24_Reinforced_Concrete_Pier_Cap	2.1 MAT-C-Special Aggregates for Reducing S	GENENT: Type II-M Transform Schools (C,S) PLYASH: AGTM CA Dealcram Schools (C,S) HYDRATION STAB Tritecture. Abundrate (WATER DEPORTORY Tetrasticution: Abundrate (Report On: Concrete Compressive
a. Prepare, cast, and deliver to	ot ✓ 📕 25_CIDH	2.1 MAT-D-Concrete Admixtures and Cementin	HIGH END WATER 2 (COA) + CIAT, N (AGTM C 1009) Teparts	Project: G17201.01 Acct ID: G172 Page 1 of 3 Client: Project: Calfornia High Sceed Rail Construction
laboratory-cured compression	te 03 05 15-PCC	2.1 MAT-E-Water.pdf	(ASDM C 402) Separate (ASDM C 400) -325 Mar (ASDM C 200) Blatter, (ASDM C114) Laneston	Package #1
C39.	yiii 03 20 00-CB	2.1 MAT-F-Reinforcement Fibers.pdf	(ASTM C114) Lanceton (ASTM C114) Censent, 1 (ASTM C 271) These of 5 (ASTM C 271) These of 5	Report Date: 09/10/2019
b. The minimum number of te	st	2.2 MAT-A-Tests and Sample Analyses.pdf	(ASTM C 151) Take Set, (ASTM C 185) As: Centr (ASTM C 181) Astrocker	Sampled By: By Order Ot: Nax Compressive Avenue
each placement shall be four o		2.2 MAT-B-Samples.pdf	(ASTM C 157) Normal ((ASTM C 199) Compres 1 Day 3 Day	Cylinder Ape Tested Diameter Area Load Cure Strength Tested Marked (dato::days) (h) (h') (Hest Break Type Loc (PSR) (PSR) By 1 0.0022/19:7 C.00 28.274 128.020 Type 2 Lab 4.560 4.560
additional sets of test cylinders tests, each set shall consist of	a 03_35_00-CF	2 3 MAT-Mix Designs ndf	7 Day 28 Day 6 This connects movels the s	2 069/2319:7 6:00 28.274 132,050 Type 2 Lab 4,670 4,620 3 069/13191:28 6:00 28.274 183,120 Type 2 Lab 6,650 4 0913191:28 6:00 28.274 193,460 Type 2 Lab 6,840 6,750 5 HOLD
c. All cylinders n a set shall be	26_05_28-G&B	3.1 EOC-A-Inspection&Test Services odf		Comments: HXLD 6 HOLD Comments: HXLD
number on the record of concr	et 📜 31_63_29-DCP&S	2 1 EOC-P 1 Methods of Sampling&Testing-San	Applicable ASTM C 15 Non 2 There are called with	Type 1 Type 2 Type 3 Type 4 Type 5 Type 6
independent testing laboratory	🚬 > 📙 040_Bearings	2.1 EOC-P.2 Methods of Sampling&Testing-Slur	mpring.put descende a content descentes () fut Neted supple served unter the pr Note C Unseters addition	Measurement Specification: 4000 pd (28 days) Weather: Temp.: Ambient: 50°F Source: Job day Transportad By: Mite: KPT 50 to 05°T Plant: Culture: Placement Disc (60°Fc2019)
at 28 days in accordance with	AS > 050 Expansion Joints	3.1_FQC-B.2_Methods_of_Sampling&Testing-Stul 2.1_FQC-B.2_Methods_of_Sampling&Testing_Cor	nip_resis.p	Arr Confect: 90 7 5 to 105 11 11 10 000 31 5 10 10 10 11 11 10 000 31 5 10 10 10 10 10 10 10 10 10 10 10 10 10
cylinder shall be discarded.		3.1_FQC-B.4_Methods_of_Sampling&Testing-Con	icrete_Onitormity.put	Quantity Represented: Placement Localium: Abutmonts 1 & 2 CIDH pics Ave 10 guideway
e. In the event the 28-day test		3.1_FQC-B.4_IViethods_of_Sampling&Testing-Ten B.4_500.055.04.000	nperature.pdf	Sampe Locaton; Entran 11945/ Remarks: Enf Proparation Markoid - ASTM C1231 Test Method (As Applicable); Compressive strength lasts per ASTM C19.
Laboratory sha n then test the		3.1_FQC-B.5_Methods_of_Sampling&Testing-Stre	ength_rests.pdf	Respectfully Submitted,
03 05 15 – PORTLAND Iontractor's Benef	CORRESPONDING "TEST CASES"	3.1_FQC-B.6_Methods_of_Sampling&Testing-Cor	tractor's_Benefit.pdf	Sec. Sec.
CEMENT CONCRETE (PCC) 1e Contractor's be		3.1_FQC-C-Evaluation_and_Acceptance_of_Tests.	pdf	
r's quality contro		3.1_FQC-D-Acceptance_of_Structure_(Completed	_Concrete_Work).pdf	NOTES, TREE REPORTS AND FOR THE EXCLUSING USE OF THE ADDRESSED CLAIM AND AND NOT TO BE REPORTED AND AND ANTI-COMPANY AND AND THE REPORT OF A DRESSED. ECOSY OF A DRESS AND A DRESS

SYSTEMS ENGINEERING ACTIVITIES PERFORMED STEP 3: VERIFICATION & VALIDATION – PERFORMING THE ACTUAL REVIEW



03 05 15 Portland Cement Concrete DL - 191 Executed	TCR		
1 GENERAL			SUBMITTAL: CONCRETE MIX DESIGN
1.6 SUBMITTALS		Concrete Mix Design	Sametri CARDON Water water and a second seco
A.Concrete Mix Designs: Submit mix designs as herein specified in Article entitled "Mix Designs"	Yes	une Drilled Sharks: We rv-te 7,80 sack, 387, FA	design studies conductors and web to interface on materials exceeded to activate. Exceptions studies and web to interface to interface on the design of the studies and the studies of the studies Hole Interface Conductors and the studies
Include laboratory test reports of trial strength and shrinkage tests. Submit mix designs a minimum of 30 days prior to batching or delivering concrete.		AGG 1: 1"* #4 Gravel AGG 2: 08"* #8 Pa d Grave AGG 3: Controle Sterid Sillerte: AGG 1: AG	The Al-SPO and Al-Show of Al-SPO CARSE BLCD 2 / % 4449 CARSE OF MEDICAL And ALE CARSE OF THE DISC ALE AND ALE CONTINUE SMARLA 491-10-003 202 Tel (2014) ALE SOURCE CONTINUE SMARLA 491-10-003
2 PRODUCTS		9/2,mm 01/4/2003 04/4 17/2 100 1/1 98 10/2	UNKG CHANNE CHANNE CALLYNE CALLYN CALLYN CALLYNE CALLYN CALLYNE CALLYN CALLYNE CALLYN CAL
		307 2.1 MAT 64 80 .	A Portand Cement MATERIAL:
A. Portland Cement: ASTM C150, Type II, low alkali. Type III Portland cement may be used	Yes	439 #63 #130	PORTLAND CEMENT
where high early strength concrete is a requirement as approved by the Contractor's engineer.		MATERIAL	-10.00 M 10.00
3 EXECUTION		CEMENT: II.VASH: (mpt GGB=Bus, (mpt AGGI: 1*2 / http: ///////////////////////////////////	CEMENT TEST REPORT ett: Preminente Type II/v. Low Alkalit, ASTM C 120-10 orden Fordel Personente August 2027 Report Date 9/7/2027
3.1 FIELD QUALITY CONTROL		AG3 2: 391 AG3 3: Con AG3 : Con WATER: MAN	STADARD CITIBUICA REQUIRIMENTS TEST ASTM (104 MSPC/IICATIONS) ASTM (114 REMITS TYPE II TYPE IV Datade 9002 N 21 10 10 10 Datade 9002 N 21 10 10 10
B. Methods of Sampling and Testing:	Yes	Hydration Stabile Eucon WH-91. Call Paradol 6400: Saga TCH41 St. Sala	Only (FMO) 5 11 FOC B.S. Methods of Bampling & Testing 1 writes USAN UKC
1. Sampling: Representative composite samples shall be taken in accordance with ASTM C172. Each sample shall be obtained from a different batch of concrete on a random basis.		DESIGN STREAM 4000 psi 42.24 Minute Acception that is a construction of the acception of the acception of the acception of the acception of the acception of the acception of the acception of th	HIGHNORDAN HIGHNO
5. Strength Tests:	Yes	PLYSER ACTM C- Daba HYPERATOR 374 WATER REDUCER TRANS	Constant CSI data Naturative I sector Naturative I Report On: Concrete Compressive
a. Prepare, cast, and deliver to the same independent testing laboratory, cylinders for laboratory-cured compression test samples. Cylinders shall be made and cured in			Project: G17201.01 Acct ID: G172 Page 1 of 3 Mic 300 Typework Glant: Project: California High Speed Rail Construction Hic 403 G29wark Railoge #1
accordance with ASTM C31. Cylinders shall be tested in accordance with ASTM			M C299 Reads in MC110 Januaria MC110 Contents MC110 Contents 9 Report Date: 09/16/2019
C39. b. The minimum number of test extinders to be made for each class of concrete and for		442 447 477	14 (219) June and 5 14 (219) June 219 14 (219) June 219 14 (219) June 220 14 (219) Ju
each placement shall be four cylinders for each 100 cubic yards or fraction thereof. When			Max Consumerative Avenage Maximum Cylinder Age Tested Diameter Area Load Cure Strength Strength Tested Marked (date : days) (th) (th") (test) Break Type Loc (+93) (+93) By
additional sets of test cylinders are required beyond the normal 7- and 28-day			3 Der 1 0623419:7 6:00 28:24 120,00 Type 2 Lab 4,600 7 Der 2 0623419:7 6:00 28:24 120,00 Type 2 Lab 4,670 4,620 3 Der y 3 0641319:78 6:00 28:74 132,00 Type 2 Lab 6,650 4 041319:28 6:00 28:74 19:4,60 Type 2 Lab 6,650
c. All cylinders in a set shall be marked with a unique number on one end. Record this		OF COMPLIANCE	5 HOLD Comments (OLD 6 HOLD Comments (OLD
number on the record of concrete placed. All cylinders shall be cured by the Contractor's		August 100 million and	Locale ACTION C 400 T/pe 1 Type 2 Type 3 Type 4 Type 5 Type 6 Type 1 Type 1 Type 2 Type 3 Type 4 Type 5 Type 6 Type 1 Typ
d. From each set of cylinders cast, one cylinder shall be tested at 7 days and two cylinders		demon	Device working Device memory Specification: 4,000 ps/ 6g/ 2g/ 6g/ ys Weather: Change working Temp.2 Ambient Soft F Source: 3.05 million Transported by: Change working Milz KEY Solid Int 197 Plant: Contacks: Plant: Contacks: Unwardworking Milz KEY Solid Int 197 Plant: Contacks: Plant: Contacks:
at 28 days in accordance with ASTM C39. If the 28-day tests are satisfactory, the fourth			Air Contient: Was Code: 49 5027 I Time Sampfield: 10/20 am Tickat Nos 66722 Sampled At: Pump Carring Mathod: Standard
e. In the event the 28-day tests are below the specified strength requirements, the			Quantify Representation: Abutronits 1 & 2 CIDH pics Are 10 guidoway Sample Location: STRike ITH445 Nemarks: Elic Program Method . ASTM 01231
Laboratory shall then test the fourth cylinder at the age selected by the Contractor's			Test Nethod (As Applicable): Compressive strength tests per ASTM C19 Respectively Submitted,
03 05 15 - PORTLAND			
CEMENT CONCRETE (PCC) In Contractor's benefit, shall be performed at Contractor's expense as part of	-		THE INFORMATION OF THE EXAMPLEMENT OF THE EXAMPLEME
r's quality control program.			THE QUILTER DE ANALYSE IN REFERIDU OR ANALYSE REPORTED DE PORTUGERE, UND DO INVERTENDE NA DECOMO UNE A DUBLICE DE DUBLICE DUBLICE DE DUBLICE DE DUBLICE DE DUBLICE DE DUBLICE DE DUBLICE DE

SYSTEMS ENGINEERING ACTIVITIES PERFORMED STEP 4: TRACEABILITY – USING REQ. MGMT. TOOL (AUTOMATED TRACING)





SYSTEMS ENGINEERING ACTIVITIES PERFORMED STEP 4: TRACEABILITY – INHERENT TRACEABILITY (W/O RM TOOL)



		4		
03 05 15 Portland Cement Concrete DL - 191 Executed	/	1.6_SUB-A-Concrete_Mix_Designs.pdf		SUBMITTAL:
1 GENERAL		1.6_SUB-B-Product_Data.pdf	Concrete Mix Design	CONCRETE MIX DESIGN
1.6 SUBMITTALS		1.6_SUB-C-Aggregate_Source.pdf	DATE 7/6/16 PMDACT California High Speed Pall - CP12	Internets, CARADINATION INTERNET, INCOMENDATION AND ADDRESS AND ADDRE
A.Concrete Mix Designs: Submit mix d	esigns as herein specified in Article entitled "Mix	1.6_SUB-D-Certificates.pdf	USE Drilled Shafts: Wet Hole discours	Middauba Markit na rubez, miesten Midzel na odkowi za konjekti kon zajstvali na Na se na se na na na se na Na se na s Na se na s
Include laboratory test reports of trial	strength and shrinkage tests. Submit mix design	1.6 SUB-E-Batch Tickets.pdf	AGG 1: 1* x H Gravel The A AGG 2: 36* x H8 Poa Gravel B AGG 3: Concrete Sand CH8	ILEND That SIL The second ADD ADD ADD E LEND To 1' S ANY DOUBLE CONTRACT ADD ADD ADD ADD ADD ADD ADD ADD ADD AD
minimum of 30 days prior to batching	🗸 📜 8.0 Quality	1.7 OAC-A-Qualitied Concrete Supplier.pdf	SIEVE AGG 1: AGG 2: RF/H SIZE, mm BRADING GRADING GR 1 1:2* 100 100 Prest	HAND REAL CONTRACT CONTRACT HAND REAL CONTRACT CONTRACT CONTRACT HAND REAL CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT HAND REAL CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT HAND REAL CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT HAND REAL CONTRACT CONT
2 PRODUCTS	✓	1.7 OAC-B-Concrete Supplier.pdf	17 99 100 Signe 344 80 100 Signe 1/2° 349 2.1 MAT - A - Portland Cer	100 3019 5010 X J
2.1 MATERIALS	> 010 Structure Wide	1.7 OAC-C-Mix Designs.pdf	24 98 715 20	MATERIAL:
A. Portland Cement: ASTM C150, Type		1.7 OAC-D-Contractor's Quality Management	#50 #100 #230	
where high early strength concrete is	M D20 Substructure	1.7 QAC-E-Cement and Aggregates.pdf	MATERIAL CEMENT:	CEMENT TEST REPORT
3 EXECUTION		1.8 ENV-A-Hot Weather Concreting.pdf	FLYASH: (np) GGBF Slag: (np) AGG 1: 1"x: Production Particul Para	e Type I(V, Low Alkalit ASTM C 150.16 mmeth Agust 2017 Repet Date 9/7/2027
3.1 FIELD QUALITY CONTROL	21_Reinforced_Concrete_Columns	1.8 ENV-B-Cold Weather Concreting.pdf	AGG 2: 3/8°: STAND: AGG 3: Cont AIR: Matter: Materia Diodate (NCU), X WATER: Materia Diodate (NCU), X	ARD CHIMCAL REQUIREMENTS TEST ASTAC (19) 45 SPECIFICATIONS ASTA C 114 REBAITS TYPE II TYPE V 5 21.0
B. Methods of San pling and Testing:	> 22_Reinforced_Concrete_Abutmen	2.1 MAT-A-Portland Cement.pdf	Hydration Stabilie Euron WR-91: Calcture Oxide (CeO), % Euron WR-91: Calcture Oxide (CeO), % Stagnester: Oxide (CeO), %	3.1 FOC 8.5 Methods of Sampling & Testing . (
1. Sampling: Representative composit	> > 23_Reinforced_Concrete_Pile_Caps	2.1 MAT-B-Aggregates.pdf	101ALS: Subar Transide (SO,) % DESIGN STRENK Loss on Ignition (CO), % 4000 psi at 28-da AGGERGATES: AS Alcolas (NG) averaged	FIELD QUALITY CONTROL:
Each sample shall be obtained from a	>] 24_Feinforced_Concrete_Pier_Cap:	2.1 MAT-C-Special Aggregates for Reducing S	CENENT: Type II-V FLYASH: AGTM Co HYDRATION STAB Tricalcton Alternitiate IC	STRENGTH TEST
a. Prepare, cast, and deliver to t		2.1 MAT-D-Concrete Admixtures and Cementit	WATER REDUCES HIGH END WATER (ACTIM C 1009) Teparate	Project: G1720101 Acct ID: G172 Page 1 of 3 Teach Of Base 1 of 3 Teach O
laboratory-cured compression te	03.05.15-PCC	2.1_MAT D Condicte_Admixtures_and_cement	(ASTM C 452) Expension (ASTM C 430) - 325 Mart (ASTM C 234) Blaine, m	Project: California High speed kai Construction Package #1
accordance with ASTM C31. Cyli		2.1_MAT-E-Poinforcement Eibers odf	(ASTIM C114) Envedorer (ASTIM C114) Envedorer (ASTIM C114) Censent S (ASTIM C114) Censent S	Report Date: 09/16/2019
b. The minimum number of test	03_20_00-CR	2.2 MAT A Tests and Sample Applying off	(ASTM C 291) Time of 5 (ASTM C 101) Table Set, (ASTM C 105) Att Control (ASTM C 105) Att Control	Location: Fresho and Madera County HSR Route CP 1 Sample Date: 06/16/2019 Sampled By: By Order Of:
each placement shall be four cyl	03_30_00-CIP	2.2_MAT-A-Tests_and_sample_Analyses.pdf	(ASTM C 107) Normal C (ASTM C 107) Normal C (ASTM C 109) Campros	Max Compressive Avenue Cylinder Age Tested Diameter Area Marked (dato::days) (lin) (in') (lin) (in') (line) Break Type
additional sets of test cylinders a	03_35 <u>\</u> 00-CF	2.2_MAT-B-Samples.pdf	S Day 7 Day 25 Day (p	1 0002319:1 0.00 22.14 120.00 7/952 1.00 4.000 2 0002319:1 0.00 22.14 120.00 7/952 1.00 4.670 4.620 3 0011110:28 6.00 22.174 188,170 7/962 1.00 6.650 4 0011110:28 6.00 22.174 103.40 7/952 1.00 6.680 6.750
tests, each set shall consist of a	. 26_05_2∂-G&B	2.3_MAT-Mix_Designs.pdf		5 HOLD Comment: (K) D 6 HOLD
number on the record of concret	31_63_29-DCP&S	3.1_FQC-A-Inspection&Test_Services.pdf	Applicable ASTM C 153	
independent testing laboratory.	> 040 Bearings	3.1_FQC-B.1_Methods_of_Sampling&Testing-Sam	pling.pdf the provide of a content demonstrated by Test Nettod supples content uncer the pro	Measurement Specification Specification Specification: 4,000 pd ⊗ 28 days Weather: Temp.: Ambient: 50°F Source: Abb site Transported By: Mass F0°F Source: Abb site Descenario Dy 70°15°10°
d. From each set of cylinders ca at 28 days in accordance with Al		3.1_FQC-B.2_Methods_of_Sampling&Testing-Slum	np_Tests.p	Shimp: 9.0 7.5 to 10.5 TruckNo: 11 Trini Battoria Via Air Content: No. 2.5 to 10.5 TruckNo: 11 Trini Battoria Via Air Content: No. Code: 405 5027 Tiene Sampled: 10.20 em Ticket No. 62322
cylinder shall be discarded.		3.1_FQC-B.3_Methods_of_Sampling&Testing-Cond	crete_Uniformity.par	Sumpled Al: Pump Caring Method: Standard Quantity Representati:
e. In the event the 28-day tests	> 📕 060_Polystyrene	3.1_FQC-B.4_Methods_of_Sampling&Testing-Temp	Sample Location: STR00 TM2 and the Location processor of Locationary Sample Location: STR00 TM201 Additional ASTM 01231 Test Method (A Applicable): Comprisable strangt lists par ASTM 039	
Laboratory shall then test the fea	> - 070_Utilities	3.1_FQC-B.5_Methods_of_Sampling&Testing-Stree	ngth_Tests.pdf	Respectfully Submitted,
03 05 15 – PORTLAND Contractor's Repetit	> 📙 080_Lighting	3.1_FQC-B.6_Methods_of_Sampling&Testing-Cont	tractor's_Benefit.pdf	
CEMENT CONCRETE (PCC) le Contractor's ben	efit, shall be performed at Contractor's expense	3.1_FQC-C-Evaluation_and_Acceptance_of_Tests.p	df	
r's quality control p	program.	3.1_FQC-D-Acceptance_of_Structure_(Completed_	Concrete_Work).pdf	THE BUILDER OF REPORTS AND ADDRESS OF REPORTS IN TRANSPORTS IN PROCEEDIngs IN THE ADDRESS ADDRES ADDRESS ADDRESS ADDRESS ADDRESS ADDRESS





- Problem Statement & Offered Solution
- Background & Introduction
- Systems Engineering Challenges Faced
- Systems Engineering Objectives
- Systems Engineering Activities Performed
- Summary, Achieved Outcomes & Conclusion

SUMMARY





ACHIEVED OUTCOMES & CONCLUSION



Addresses the Systems Engineering Challenges

- Implemented pilot project for Ave 10 Roadway Overhead as proof of concept
- Enabled reviewers to efficiently and effectively identify relevant quality records
- Produced excellent review comments against construction specification requirements

Avoids the cautionary tale of the Big-Dig scenario

 Provides a requirement-based approach demonstrating the correct use of specified materials and the successful execution of all specified inspections and tests

Will Delivers the successful HSR Milestones Acceptance and Certification

- Offers the assurance that the infrastructure HSR milestones have been built in accordance with the construction specifications
- Will lead to successful acceptance, certification, and handover to the next HSR track and systems contractors, thereby reducing performance, schedule, and cost risk to the Authority and the public

Demonstrates the Professional Standard of Care

 Structured & systematic application of systems engineering principles to construction specifications illustrates the systematic exercise of a reasonable level of care, diligence, and skill, referred to as the professional standard of care, thereby demonstrating the Value of Systems Engineering as a successful liability protection and risk mitigation strategy



www.incose.org/symp2021