Systems Engineering the World's Most Energetic Laser

Robert Plummer Chair, Systems Engineering Board, LLNL

LLNL-PRES-797760

March 2023

This work was performed under the auspices of the U.S. Department of Energy by Lawrence Livermore National Laboratory under contract DE-AC52-07NA27344. Lawrence Livermore National Security, LLC



Robert Plummer

- Chair of LLNL Systems Engineering Board
- Chief Engineer for Advanced Photon Technologies within NIF&PS and Project Engineer for the MEC Rep-Rated Petawatt Laser Upgrade for SLAC LCLS
- Formerly Head of Engineering & Maintenance for NIF Optics
- Technical expertise in structural mechanics, machine design and integration, systems engineering, and optomechanics
- Education
 - Systems Design and Management (SDM) Program, Massachusetts Institute of Technology
 - Masters of Science, Structural Engineering, Stanford University
 - Bachelors of Science, Civil and Environmental Engineering, Rice University





What we are going to talk about

- NIF, the world's largest and most energetic laser
- NIF's evolving history with SE
- SE in practice at NIF/case study



LLNL is a DOE national security laboratory located in SF Bay Area


Lawrence Livermore National Laboratory

- Established in 1952
- 1 square mile, >500 facilities
- ~8,300 employees
- Annual budget ~\$2.9B



Lawrence Livermore National Laboratory







Lawrence Livermore National Laboratory LLNL-PRES-797760

National Ignition Facility (NIF) is the world's largest and most energetic laser, delivering >1.8MJ and 500TW to targets







>200 building, utility, beampath, diagnostic, and laser systems
>75,000 control points
>250 offsite systems for optics and target fab

LASERS

TB

LASERS































SE at NIF: past and present





Through engineering best practices and process, SE is built into everything we do at NIF



Design Reviews

| arch fund | ery and level Sua | | Idennood Search | | | | | | | | 0 |
|-----------|-------------------|-----|------------------|---------------|-------|---------------|------------|-------------|------------|-----------------------|-----------------------|
| Differen | | | -Mitger, and a | | | | | | | Sant a Nav S | ante Section Sociali |
| * Searce | ch Results 0 m | | | | | | | | | | 120 dga 51 |
| E | S | X . | tin The bases of | The Arthur | | | | | | Generation | 81.0 |
| 0 | | | Number of | Nors | | Contant | izotin | 20101 | bes | Lot ModPer | Currie Cr. |
| | - 69 | | 10000-001627 | 34409-101087 | G) | 133,309 | 100,009 | AN Designs | in work | 20 4 40 42 22 30 901 | 2010 12 12 12 12 17 |
| | | | | AND YOURS | æ | 140,08 | ORD, NOV | AS 1 SMIGHT | in vites | AT 1 10 \$7.23 KHO | 2814 12 10 11 27 10 |
| | 0 | T | ANALY INTERACT | AVEN 3 PART | - (3) | NUCLEA | 1940,549 | ALCOHOL: | In vitrals | 40-2108300 | VEH D' D'DO'S PO |
| 5 | \$ | P | AAAD.IIII-H | 332H 3794K | 0 | 190.08 | 190.50 | All Through | 1127-12 | 10-010-00101 | 2010/07/07/02/09 |
| τ. | 4 | 1 | BARTATING. | 33275.37964 | G | 190.00 | 190 300 | AC TROUGH | Delmos. | 315/1291291951 | 2010.01-00 3548 797 |
| τ. | 01 | | AARD-THEN | AMON-101854 | (2) | 1580,200 | 1900 0000 | AR DOARD | Section 8 | 2020-02-02-02-01 1937 | 2009-62-61 1919 707 |
| Ε. | 0 | | 44422-101028 | AA400-101055 | 02 | 1583,2000 | /1500_2080 | AA Designa | In Work | 2010-02-09-00 11 PST | 2305-62-61 10:25 757 |
| 6 | | | 44425-10167 | A4409-101087 | (2) | 130,200 | /1500_2009 | Ak Deigni | In Work | 2010-02-09-00-01 PST | 2009-02-02 02:25 7:57 |
| | 69 | | ANAIS-10168 | 34409-101285 | 3 | 124.0,2806 | 430.0,2089 | AN Deriges | in Work | 2019-02-09-02-11 P57 | 2008-02-02 10:28 PST |
| | - 60 | | AAA39 101698 | AA108 101389 | æ | 123,000 | 18.0,2089 | AR Designa | TO VEHICLE | 2009-02-02-02-01-957 | JON 62 GL SALS FET |
| 5 | - 62 | 1 | ANNIN TETA O | AAGEN STRAC | 0 | 140,08 | 100,000 | AN COMPANY | 11/2015 | ABOUTERSON | SERVICENT |
| 5 | 8 | | 55539 1218-0 | AMER STRAS | G | 190,08 | 190,504 | AL 19-101 | 10294 | 10-21082-01 | SERENERATION |
| 2 | \$ | | - | 0007437944 | G | 190.08 | 090.50 | A5.1 21-101 | 1412143 | 10021022191 | 104050101010 |
| 2 | 0 | | 4442-111EE | A465.10185 | 3 | 1993 (000 | 1940 2080 | A5 * 25-341 | 110541 | 2012-02-05-02-021951 | 200542-01314707 |
| 2 | Q2 | | AAA23-101636 | AA405-101855 | (8 | 1.920,2000 | -1500_2080 | AA DOOM | In Work | 2010-02-05-00 12 197 | 2005-02-02 11:14 757 |
| ۲. | Q2 | | 4442-0161 | A4409-101251 | | 1580,2005 | -1500_2009 | AA Dolgri | In Work | 2010-02-09-09-12-957 | 2005-02-02 11:14 757 |
| | 63 | | AAA20-1110-0 | 344009-101040 | (B) | 1.2K.D., 2006 | /1500_2009 | All Deliger | Its Work | 2010-02-09-00 12 757 | 2009-02-02 11:14 707 |
| | - 59 | | | 34409-101054 | 0 | 122,200 | 1210_2009 | AS Designs | IN VIOL | | 2009-02-02 8 114 PDT |
| | 60 | | | AND DESC | a | 140,000 | 120,009 | As people | in your | 2009/02/02/02/02/02/ | 2011 02 02 10 1 10 H |
| 1 | | | ANNO 1216/16 | 0000000000 | æ | 140.08 | 090.004 | All SHOOT | none | 10/01082/01 | STREET STREET |

Configuration Management





Requirements Management

| Work Authorization Point Checklist | | WAP Activity: | | | |
|---|---|--------------------------|----------------|---|----------|
| | | AI: | AL | | |
| Phase 1: Ready for Installation | Need by | RSE (RI/SM): | RSE | | |
| Phase 2: Ready for IQ | Need by | RS: | | | |
| Phase 3: Ready for OQ | Need by | | | | |
| Phase 4: Ready for Ride-a-long Shots (Ri required during operations, with TAO support provided) | Need by | | | | |
| Phase 5: Ready for turnover to operations | Need by | | | | |
| Last Updated: | | | | | |
| Standard Checklist Documentation | Deliverables | Provider | Phase Req'd | Reviewer | Approval |
| Management Oversight | | | | | |
| Work Authorization Scope | Scope Summary / Checklist | RSE | 1 | AI | |
| | | | | | |
| Work Authorization Scope Review | Scope Summary / Checklist | S&PRB Coordinator | 1 | S&PRB Reader | |
| Work Authorization Scope Review Authorized Safety Basis | Scope Summary / Checklist SBCC Checklist | S&PRB Coordinator RSE | 1 | S&PRB Reader Safety Analyst (Watson) | |
| Authorized Safety Basis | | | 1 1 1 | | |
| | SBCC Checklist Integrated Work Schedule Planned (SubFLIP & TAO Daily | RSE | | Safety Analyst (Watson) | |
| Authorized Safety Basis Facility Schedule | SBCC Checklist Integrated Work Schedule Planned (SubFLIP & TAO Daily Plan) | RSE | 1 | Safety Analyst (Watson) Facility Coordinator (Cox) | |

Work Authorization Process



Design reviews are conducted to solicit independent, peer review in order to identify and manage risk

- Checklist-driven process ensures consistency and thoroughness
- Categories
 - Project mgmt.
 - Risk mitigation
 - Requirements
 - Physics basis
 - Procurement
 - Documentation
 - Verification testing

| | , 0 | | | | | | | |
|---------------|--|---------|-------|-------|-------|------------|------------|--|
| GRP | Deliverable | RQMTS 💌 | CDR 🔻 | PDR 🔻 | FDR 💌 | Provider 💌 | Reviewer 💌 | |
| | Project milestone scope, deliverables, and design review goals defined | x | x | x | x | | | |
| | Cost, incl. basis of estimate, budget, % spent, projection, etc. | × | x | x | x | | | |
| Project Mgmt. | Operating costs assessed (operations labor, consumables, etc.) | | | | х | | | |
| ect | Schedule, incl. link to other program/external milestones | x | X | X | Х | | | |
| 2 | Labor plan, incl. external resource needs | | Х | Х | Х | | | |
| - | Document feedback for future projects of related or similar scope | | | | x | | | |
| | Turnover scope for Work Authorization Point (WAP) defined | | | | х | | | |
| Aitigation | Action item plan from previous reviews | X | x | X | x | | | |
| | Lessons learned from previous or related projects | х | Х | | | | | |
| | Open issues and problem logs (i.e. LoCoS, JIRA, ITS, etc.) | х | X | | | | | |
| | Failure Modes and Effects Analysis (FMEA, see NIF- 5020855) | D | F | delta | delta | | | |
| | FMEA reviewed by CM Working Group for impact to Configured Systems & Configured Items (see NIF-0015684) | | | D | F | | | |
| Risk n | By satisfying the performance requirements, does the | D | x | х | F | | | |
| 2 | system create additional risk for other systems, personnel, or the environment? | | | | | | | |
| | Physical security, electronic security, export control, and classification risks | | D | F | delta | | | |
| | Hazardous materials risks incl. radiation, waste, sampling, and monitoring | | D | F | delta | | | |
| | Stakeholder expectations gathered (via interviews, etc.) | F | delta | delta | | | | |
| | Concept of Operations, use-case scenarios, and context diagrams defined | x | D | F | delta | | | |

Stakeholder analysis and interface management prevalent; reviews tailored to risk



Single database serves as repository for requirements mgmt.

| Title | Properties Proposed Changes Relationships Attachments Traces Advanced Branches Labels Workflow History Requirement Color Separation Grating |
|----------------------|--|
| | Requirement fext The color separation grating shall have an efficiency of > 95% at 3w and 1% at 1w/2w and should have an efficiency of > 98% at 3w and 0.5% at 1w/2w. The grating period shall be chosen consistent with the unconverted light management strategy. (diffractive optics plate) |
| | WBS Number NL.3.2.1.9 WBS Title 3w Diffractive Optics Plate (3wDOP) LRU's Text Rigor Level Validation Method Text State Chaproved Approved Date Nov 19, 2015 9:45:48 AM Text |
| Product Breakdown | Project NUF (Proposed) Revision Additional Comments [dreimer, Aug. 3, 2015 3:26:40 PM PDT] No longer a CSG Requirement Basis |
| Structure (PBS) | Subscribe Subscribed Users List |
| Basis & | Requirement Name 5502527-0A SDR/SSDR Basis 0000439-0C Date of Last State Change - Requirement Verification - Keywords Optical Project/Program N/F - N/E Requirement |
| Traceability | Project/Program NIF - NIF Requirement USH |

Requirements are an OUTCOME of the SE process, *not* the beginning of the project





Configuration management platform for all system documents

- Revision control
- Workflow approvals
- Check-in/checkout system

Drawings, procedures, memos, test plans and reports, risk assessments, design reviews, etc.

| << Edit | | | | | | | | | | | 0 |
|---------|------------------------|----------|----------------------------------|--------------|-----|----------------|------------|---------------|---------|----------------------|-----------------------|
| | | | rpe= All Types ;Context=# | | | | | | | Start a New Se | arch Save This Search |
| b | | × | Add to Workspace Add | Actions - | | | | | | Search in table | (215 objects) |
| ору са | III MUILIPIE Objects D | elete M | Number | Name | | Context | Location | Version | State | Last Modified | Created On |
| | | | | AAA09-101687 | | LSEO 2009 | /LSEO_2009 | AA.1 (Design) | In Work | 2014-03-12 23:38 PDT | · · - |
| | چ. چ | | | AAA09-101686 | i | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | 2014-03-12 23:38 PDT | ^ |
| | | | _ | AAA09-101634 | i | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 07:48 PST |
| | ې چې | | | AAA09-101633 | i | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 07:48 PST |
| | <u>م</u> | | _ | AAA09-101644 | i | LSEO_2009 | /LSEO_2009 | AC.1 (Design) | Release | | 2010-11-30 14:45 PST |
| | ي. چ | | | AAA09-101694 | (i) | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 18:29 PST |
| | <u>م</u> | | | AAA09-101698 | (i) | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 18:29 PST |
| | <u>چ</u> | | | AAA09-101697 | (i) | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | 2009-02-03 00:01 PST | |
| | ی ش | | | AAA09-101695 | (i) | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 18:29 PST |
| | ÷. | _ = | _ | AAA09-101699 | i | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | 2009-02-03 00:01 PST | |
| | 6 | 7 | AAA09-101652 | AAA09-101652 | i | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 11:14 PST |
| | <u>iii</u> | F | AAA09-101655 | AAA09-101655 | i | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 11:14 PST |
| 1 | | | _ | AAA09-101646 | i | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 11:14 PST |
| | | | | AAA09-101650 | (i) | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 11:14 PST |
| | | | _ | AAA09-101656 | i | - LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 11:14 PST |
| | ÷ | | _ | AAA09-101651 | i | | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 11:14 PST |
| | \$ \$ | | _ | AAA09-101648 | i | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 11:14 PST |
| | \$ | | _ | AAA09-101654 | i | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 11:14 PST |
| | | F | AAA09-101653 | AAA09-101653 | i | LSEO_2009 | /LSEO_2009 | AA.1 (Design) | In Work | | 2009-02-02 11:14 PST |
| | | | AAA09-101649 | | (i) | | /LSEO 2009 | AA.1 (Design) | In Work | 2009-02-03 00:02 PST | • |



Once design lifecycle completed, authorization to field on NIF granted through Work Authorization Process (WAP) or Point


| Work Authorization Point Checklist | | WAP Activity: | | | |
|--|--|---------------------------------|----------------------|---|----------|
| | | AI: | AI | | |
| Phase 1: Ready for Installation | Need by | RSE {RI/SM}: | RSE | | |
| Phase 2: Ready for IQ | Need by | RS: | | | |
| Phase 3: Ready for OQ | Need by | | | | |
| Phase 4: Ready for Ride-a-long Shots (RI required during operations, withTAO support provided) | Need by | | | | |
| Phase 5: Ready for turnover to operations | Need by | | | | |
| Last Updated: | | | | | |
| | | | | | |
| Standard Checklist Documentation | Deliverables | Provider | Phase Req'd | Reviewer | Approval |
| | Deliverables | Provider | | Reviewer | Approval |
| | Deliverables | Provider RSE | | Al | Approval |
| Management Oversight | | | Req'd | | Approval |
| Management Oversight Work Authorization Scope | Scope Summary / Checklist | RSE | Req'd | AI | Approval |
| Management Oversight Work Authorization Scope Work Authorization Scope Review | Scope Summary / Checklist Scope Summary / Checklist | RSE S&PRB Coordinator | Req'd 1 1 | AI S&PRB Reader | Approval |
| Management Oversight Work Authorization Scope Work Authorization Scope Review Authorized Safety Basis | Scope Summary / Checklist Scope Summary / Checklist SBCC Checklist Integrated Work Schedule Planned (SubFLIP & TAO Daily | RSE S&PRB Coordinator RSE | Req'd 1 1 1 | AI S&PRB Reader Safety Analyst (Watson) | Approval |

Used widely for shot campaigns, construction projects, diagnostic instruments, etc.






Following reorg in 2000, SE was introduced as critical oversight and support function for overall NIF program





Conscious decisions were made w.r.t. responsibilities based on numerous models; PM intentionally separated from SE




Much like today, early SE at NIF was part discipline, part creativity





SE provided expert groups and IPT functions to solve cross-cutting challenges within infrastructure, optics, materials, controls, laser, and targets



SE IPTs maintained

- Requirements flow-down and interfaces
- Technically responsibility



Some key elements of NIF's historical SE culture

Part discipline, part creativity

| | Requirements management and change control Verification & validation testing Discipline for documentation Daily integration and planning coupled with Work Authorization Process | iscipline |
|---|--|------------|
| • | Reward people for broaching project risk and failure modes — Maintained 300-item risk register with mitigation strategies — ~\$200M scope associated with risk mitigations | |
| • | Dynamic, organizational flexibility to manage extraordinary risk (e.g., IPTs, expert groups) | Creativity |
| • | Innovate solution and paradigm shift for grand challenges (e.g., optics refurbishment loop, optomechanics) | |



Real systems engineering at NIF





NIF optics recycling loop employs System of 50+ Systems (SoS) to characterize, mitigate, and repair damage on optics



Significant challenge to integrate SoS interfaces across multiple design teams and years

CISR2 optics polisher presented a significant CONOPS challenge to integrate all required functions smoothly

- Production machine with R&D capabilities
- Simultaneously polish two NIF-sized optics
- Leverage lessons learned from legacy systems

A mature CONOPS drove several innovative design solutions





Modular add-on assemblies for ultrasonication and pad conditioning

Air-bearing loader to change polishing pressure weights


"Pizza peel" to safely remove optics under suspended load


CONOPS was developed after 6 dedicated user interviews focusing on legacy system use cases



Lawrence Livermore National Laboratory


Critical decision made early to raise enclosure 3" to account for unknown design of optic backing plate







Prior to NIF construction, systems level assessment was performed of the many sources that affect NIF optical motion




Lawrence Livermore National Laboratory

LLNL-PRES-797760




Ambient vibration measurements were performed







Hybrid reinforced concrete and steel optical support structures were designed to enhance vibrational stability







Switchyard spaceframe attaches to the corners of the building





careers.llnl.gov

