



30th Annual **INCOSY**
international symposium

Virtual Event
July 20 - 22, 2020


Managing Integration and Verification Risks of the SKA Radio Telescope

Richard T. Lord



Overview

- Introduction to the SKA
- Integration & Verification Planning
 - Managing risks an underlying theme
- MeerKAT Precursor Integration



What is the SKA?






An international effort,
to build the world's largest Radio Telescope.

One of the largest scientific endeavours in history!



SKA Science Book 2015



- 135 Chapters
- 2000 pages, 8.8 kg
- Plus new science directions that continue to emerge!



15 Participating Countries



- 1) Australia
- 2) Canada
- 3) China
- 4) France
- 5) Germany
- 6) India
- 7) Italy
- 8) The Netherlands
- 9) New Zealand
- 10) Portugal
- 11) South Africa
- 12) Spain
- 13) Sweden
- 14) Switzerland
- 15) UK



 SKA Members
*SKA Observatory founding members




 African Partner Countries

The SKA Observatory is being established as an Intergovernmental Organisation, taking over from the SKA Organisation. It will undertake the construction and operation of the SKA telescopes.



1 Observatory

3 Sites, 2 Telescopes, 1 HQ



SKA Headquarters





Sites in Australia and SA



- SKA1-LOW: 50 – 350 MHz
- Phase 1: ~130,000 Antennas
- Across 65km



- SKA1-MID: 350 MHz – 24 GHz
- Phase 1: ~200 15m Dishes
- Across 150 km





SKA – Phase 1

- Currently at the end of the Design Phase
- 9 Design Consortia
- > €200M, >500 engineers and scientists
- Construction: 2021 – 2028
- Cost of Construction + 10 Years Operation: ~ €1.7 Billion
- MeerKAT will be integrated into SKA1-MID

SKA – Phase 2 (2030s?)



**SKA-Low: ~500,000 low-freq dipoles,
200 km baselines
Murchison, Western Australia**




AUSTRALIA

SOUTH AFRICA




**SKA-Mid: ~2000 x 15m dishes
3500 km baselines
Karoo, South Africa**

**+ Mid-Frequency Aperture Array?
+ Phased-Array Feeds?**







SKA1-Low: Array of Arrays



256



512



SKA1-Low
Antenna/Receptor

Antenna Beam

SKA1-Low
“Station”

Station Beam

SKA1-Low
“Array”

**Correlation and
Tied-array Beams**




SKA Organisation → SKA Observatory

- SKA Member governments are negotiating the establishment of an **Inter Governmental Organisation (IGO)**, similar to ESO/CERN/ITER/ESA.
- Will provide:
 - Long-term government commitment and funding stability
 - Availability of Privileges and Immunities for members
 - ‘Freedom to operate’, specifically through procurement process
- Critical step to allow SKA Observatory to operate as an international scientific facility

Seven members signed IGO
Convention in Rome, 12 March 2019

The Netherlands, Italy and South
Africa already ratified the SKA
Convention





Integration & Verification Planning



It's all about Managing Risk

- Are we building the right thing?
 - Validation of the Design
- Are we building it correctly?
 - Verification of Requirements


AIV Consortium



SARAO led the AIV Consortium



I&V Planning – Key Outputs






SKA Challenges

- Unprecedented Scale
 - Distance of 150 km between two SKA1-MID Dishes
 - Enormous amount of data traffic
 - Fastest supercomputer
- Co-Hosting
 - SKA1-MID in South Africa's Karoo
 - SKA1-LOW in Western Australia's Murchison Shire
- A global effort
 - Fifteen participating countries
 - 500 engineers and scientists
 - from around 100 organisations
 - in 20 countries

The V-Diagram



Product hand-over process is important



Product Hand-Over Process

- Important quality gate
- Well-tested products -> less system I&V issues
- Factory Acceptance Testing
- On-Site Acceptance Testing
- Product can be supported and maintained after hand-over



Subsystem CDRs

- Should provide evidence that design requirements have been met
 - Heavy reliance on analysis
 - Interfacing products do not exist
 - Simulators/Emulators might mask problems
 - Prototype hardware used
 - Different levels of rigor applied
- ⇒ System-level risks remain, even after product-level designs have been qualified
- ⇒ Qualify aspects of the design at system level early during construction



System Integration Test Facility (ITF)

- Line-up of products to (partially) qualify the system-level design
- Convenient environment to
 - install products
 - integrate with other products
 - test product-to-product interfaces
 - troubleshoot issues, etc
- Verify new releases of software/firmware (and hardware), before installing on-site
- Knowledge transfer between contractors, engineers, AIV Team, Science Commissioning Team, etc



Roll-Out Plan


- Forms the basis for the delivery of products and planning of integration & verification activities
- Considers:
 - Sequencing of implemented functionality
 - Scale: How many Dishes / Stations deployed and when
 - Integration of MeerKAT Precursor into SKA1-MID
- Sequential process – early retirement of risks
- Achieved by specifying “Array Assemblies”




Array Assemblies


- Fixed number of Dishes / Stations
 - Determined by Correlator size
 - But: Flexibility regarding *which* Dishes / Stations
- Defined Capability / Functionality
 - Basis for the delivery of products and planning of I&V activities
 - Informed by the risks that need to be mitigated
- Start Date
 - When all AA components are available
 - But: Maintain I&V flexibility regarding exact product delivery date

Sequential Roll-Out



- Verify the system in stages
- Detect problems early
- Apply design changes early








Rolling out Software

- Scaled Agile Framework (SAFe ®)
- An agile process that allows scalability of overall team size by having “teams of teams”
- 3-month “cadence” called Program Increment
- Release on demand, develop on cadence
- Continuously builds value and reduces risk
- Has an evolving architectural runway
- Working product demonstrated frequently
- Regular stakeholder engagement




Rolling out Software






Roll-Out of MID Configuration


Batch #1 (8 Dishes = AA1)




Batch #3 (+20 Dishes)



Batch #2 (+4 Dishes)



Batch #4 (+32 Dishes)



Considerations:

- Verification and commissioning requirements
- Minimisation of costs
- Infrastructure constraints, including the roll-out of PV stations




Verification Requirements

- High-level description of how each requirement will be verified
- At what level of system integration the verification will be performed
 - System ITF, AA0.5, AA1, AA2, AA3, AA4
- Who is responsible for executing the verification
 - AIV Team, Science Commissioning Team, etc




Verification Model






Verification Events




Integration Events





Verification Flow



- Sequencing of milestones and dependencies
- Factory Acceptance Tests
- Delivery of hardware or software to site
- Site Acceptance Tests
- Major Verification Events
- Hand-over of responsibility from product contractor to SKAO

Useful to ensure that there are no gaps in the verification planning

Initiated by L. Stringhetti



Test Procedures


- Exported directly from CORE
- Full traceability is given with regard to:
 - The originating System (Level-1) Requirement
 - The derived Verification Requirement
 - The Test Procedure executing the Verification Requirement
- Commissioning Tests
 - No traceability to System (Level-1) Requirements
 - But needed to commission the system
- Most tests are repeated at future Array Assemblies



Integration & Verification Plan

- Provides a structured framework, in which all integration and verification activities will be carried out in a coordinated manner
- Identifies:
 - Integration Events
 - Verification Events
- Each event has:
 - Start date
 - Duration
 - Resources
 - Prerequisites

Gantt Chart showing Verification Events





Configuration Management

- Critical to the I&V effort
- Hardware / Firmware / Software configuration status of the Telescope has to be recorded with test results



MeerKAT Precursor Integration






MeerKAT Precursor Integration

- Significant activity which carries schedule, technical and budgetary risks
- Requires careful roll-out planning
- Ensure that interfaces between MeerKAT components and SKA1-MID components are fully described



MeerKAT Precursor
Telescope Dishes

SKA1-MID Core Area





Blue Dots =
MeerKAT Dishes

Green Dots =
SKA1-MID Dishes



Integration Timeline

AA1	AA2	AA3	AA4
-----	-----	-----	-----



Ramp-up of Dishes over time

The view with an Optical Telescope




Optical image
of the famous
Fornax A
galaxy with the
MeerLICHT
telescope in
Sutherland



The view with a Radio Telescope



MeerKAT
image of the
same field of
view as in
previous slide




MeerKAT peers deep into the Universe

First radio image of distant Milky Way-like galaxies reveals star formation history of the Universe

Thousands of galaxies are visible in this radio image covering a square degree of sky

$t_i = 130$ hours

<https://www.sarao.ac.za/media-releases/south-africas-meerkat-peers-deep-into-the-universe/>





Lessons Learned

- Integrate early and often!
- Roll-out activities and AIV work scope is often under-estimated, even at product level
- Separate R&D from construction
- The value of a qualified solution is immense (much more valuable than another unproven solution that looks good)
- Learn from prototypes
- Accurate and complete requirements (that are traceable to science goals) are very important, especially when placing contracts
- Properly qualify subsystems
- Get timely and effective support and maintenance



Conclusions

- The SKA project is one of the largest scientific endeavours in history
- It needs mature processes and thorough planning in order to succeed
- The Product Hand-Over Process is important
- Develop a staged Roll-Out Plan
- Develop an Integration & Verification Plan
- Maintain Traceability
- Keep looking at Lessons Learned



30th Annual **INCOSE**
international symposium

Virtual Event
July 20 - 22, 2020

www.incose.org/symp2020