



32nd Annual **INCOSE**
international symposium

hybrid event

Detroit, MI, USA
June 25 - 30, 2022

June 30, 2022: 10:45-11:25 EDT (Track 6, Digital Engineering, Session 11.6.2)

Case Study: Using Digital Threads in a large System of Systems (SoS) for System Certification

Oliver Hoehne, PMP, CSEP, CSM
Technical Fellow, Systems Engineering
WSP USA
oliver.hoehne@wsp.com

AGENDA



❖ Introduction

- Brief System of Systems (SoS) Overview
- California High-Speed Rail System (CHSRS) Program
- Use of Digital Threads in the CHSRS Program

❖ SoSE Challenges Faced

- Systems Engineering Challenges
- SoS Engineering Challenges

❖ SoSE Activities Performed

- Certification Strategy
- Step by Step Process Description

❖ Summary, Achieved Outcomes & Conclusion

INTRODUCTION: SYSTEM OF SYSTEMS

SoS DEFINITION & CHARACTERISTICS



ISO/IEC/IEEE 15288:2015(E)

Annex G
(informative)

ISO/IEC/IEEE 15288,
2015, ANNEX G

Application of system life cycle processes to a system of systems

G.1 Introduction

A system of systems (SoS) is a system-of-interest (SOI) whose elements are themselves systems. A SoS brings together a set of systems for a task that none of the systems can accomplish on its own. Each constituent system keeps its own management, goals, and resources while coordinating within the SoS and adapting to meet SoS goals. In the context of terminology discussed in subclause 5.2.3 (as shown in Figure 3), the composite set of systems including the original SOI, enabling systems and interacting systems, together constitute an SoS. Where there are concerns that affect the composite set, the system of systems becomes the SOI, which is considered to satisfy some business or mission objective that cannot be satisfied by the individual constituent systems, or to understand emergent behavior of the combination.

This annex addresses the application of system life cycle processes to such SoS. It describes general characteristics, the common types of SoS, and the implications throughout the life cycle.

G.2 SoS characteristics and types

SoS are characterized by managerial and operational independence of the constituent systems, which in many cases were developed and continue to support originally identified users concurrently with users of the SoS. In other contexts, each constituent system itself is a SOI; its existence often predates the SoS, while its characteristics were originally engineered to meet the needs of their initial users. As constituents of the SoS, their consideration is expanded to encompass the larger needs of the SoS. This implies added complexity particularly when the systems continue to evolve independently of the SoS. The constituent systems also typically retain their original stakeholders and governance mechanisms, which limits alternatives to address the needs of the SoS.

SoS have been characterized into four types based on the governance relationships between the constituent systems and the SoS (Figure G.1). The strongest governance relations apply to directed system of systems, where the SoS organization has authority over the constituent systems despite the fact that the constituent systems may not have originally been engineered to support the SoS. Somewhat less control is afforded for acknowledged SoS, where allocated authority between the constituent systems and the systems of systems has an impact on application of some of the systems engineering processes. In collaborative SoS, which lack system of systems authorities, application of systems engineering depends on cooperation among the constituent systems. Virtual systems of systems are largely self organizing and offer much more limited opportunity for systems engineering of the SoS.

Emergence is a key characteristic of SoS – the unanticipated effects at the systems of systems level attributed to the complex interaction dynamics of the constituent systems. In SoS, constituent systems are intentionally considered in their combination, so as to obtain and analyze outcomes not possible to obtain with the systems alone. The complexity of the constituent systems and the fact they may have been designed without regard to their role in the SoS, can result in new, unexpected behaviors. Identifying and addressing unanticipated emergent results is a particular challenge in engineering SoS.

Definition: A system of systems (SoS) is a system-of-interest (SOI) whose elements are themselves systems.

A SoS brings together a set of systems for a task that none of the systems can accomplish on its own.

Each constituent system (CS) retains its own management, goals, and resources while coordinating within the SoS and adapting to meet SoS goals.

SoS Characteristics: SoS are characterized by managerial and operational independence of the constituent systems, which in many cases were developed and continue to support originally identified users of the constituent concurrently with users of the overall SoS.

INTRODUCTION: SYSTEM OF SYSTEMS

SoS EMERGENCE



ISO/IEC/IEEE 15288:2015(E)

Annex G
(informative)

ISO/IEC/IEEE 15288,
2015, ANNEX G

Application of system life cycle processes to a system of systems

G.1 Introduction

A system of systems (SoS) is a system-of-interest (SOI) whose elements are themselves systems. A SoS brings together a set of systems for a task that none of the systems can accomplish on its own. Each constituent system keeps its own management, goals, and resources while coordinating within the SoS and adapting to meet SoS goals. In the context of terminology discussed in subclause 5.2.3 (as shown in Figure 3), the composite set of systems including the original SOI, enabling systems and interacting systems, together constitute an SoS. Where there are concerns that affect the composite set, the system of systems becomes the SOI, which is considered to satisfy some business or mission objective that cannot be satisfied by the individual constituent systems, or to understand emergent behavior of the combination.

This annex addresses the application of system life cycle processes to such SoS. It describes general characteristics, the common types of SoS, and the implications throughout the life cycle.

G.2 SoS characteristics and types

SoS are characterized by managerial and operational independence of the constituent systems, which in many cases were developed and continue to support originally identified users concurrently with users of the SoS. In other contexts, each constituent system itself is a SOI; its existence often predates the SoS, while its characteristics were originally engineered to meet the needs of their initial users. As constituents of the SoS, their consideration is expanded to encompass the larger needs of the SoS. This implies added complexity particularly when the systems continue to evolve independently of the SoS. The constituent systems also typically retain their original stakeholders and governance mechanisms, which limits alternatives to address the needs of the SoS.

SoS have been characterized into four types based on the governance relationships between the constituent systems and the SoS (Figure G.1). The strongest governance relations apply to directed system of systems, where the SoS organization has authority over the constituent systems despite the fact that the constituent systems may not have originally been engineered to support the SoS. Somewhat less control is afforded for acknowledged SoS, where allocated authority between the constituent systems and the systems of systems has an impact on application of some of the systems engineering processes. In collaborative SoS, which lack system of systems authorities, application of systems engineering depends on cooperation among the constituent systems. Virtual systems of systems are largely self organizing and offer much more limited opportunity for systems engineering of the SoS.

Emergence is a key characteristic of SoS – the unanticipated effects at the systems of systems level attributed to the complex interaction dynamics of the constituent systems. In SoS, constituent systems are intentionally considered in their combination, so as to obtain and analyze outcomes not possible to obtain with the systems alone. The complexity of the constituent systems and the fact they may have been designed without regard to their role in the SoS, can result in new, unexpected behaviors. Identifying and addressing unanticipated emergent results is a particular challenge in engineering SoS.

Emergence: A key characteristic of SoS – the unanticipated effects at the systems of systems level attributed to the complex interaction dynamics of the constituent systems.

In SoS, constituent systems are intentionally considered in combination, to obtain and analyze outcomes not possible to obtain with the systems alone.


The complexity of the constituent systems and the fact they may have been designed without regard to their role in the SoS, **can result in new, unexpected behaviors.**

Identifying and addressing unanticipated emergent results is a particular challenge in engineering SoS.

INTRODUCTION: SYSTEM OF SYSTEMS

INCOSE SoS PRIMER – FURTHER READING





INCOSE Systems of Systems Primer



INCOSE-TP-2018-003-01.0

Systems tend to...	System
Have a clear set of stakeholders	Have n and po
Have clear objectives and purpose	Have n objectiv
Have a clear management structure and clear accountabilities	Have d clear av
Have clear operational priorities, with escalation to resolve priorities	Have n operati routes
Have a single lifecycle	Have n implem
Have clear ownership with the ability to move resources between elements	Have n resourc

Types of SoS
A taxonomy has evolved (proposed by Maier 1998, and extended by INCOSE 2003) and has been widely used to categorise SoS into four different types based on the degree of collaboration, noting that SoS are often complex, and may be classed differently depending on how they are viewed at, or their current operating mode at any one time.



Directed SoS are built and managed to fulfill specific goals. They have a central authority and dedicated SoS resources. Constituent systems accept that their normal operational mode is to be managed by the SoS. An example can be found in metropolitan transportation systems where services may collaborate to deliver metro service in order to participate.



Acknowledged SoS have objectives recognized by a central manager, and dedicated SoS resources. Constituent systems have their own objectives, funding, development and sustainment, but they are based on agreed collaboration. Air traffic control and safe airspace globally all recognise their shared responsibility to adhere to regulations and protocols.



Collaborative SoS comprise constituent systems with some central purposes, which can evolve based on the needs of the system. An electrical grid is an example. Autonomous collaboration between constituent systems adheres to standards and regulations, but constituent systems do not have a central authority or a central purpose.



Virtual SoS have no central authority, nor an explicit central purpose. They can exhibit large-scale emergent behavior, but they do not have a central authority or a central purpose. The Internet is an example. The Internet Engineering Task Force (IETF) standards and protocols. Independent service providers. No management or governance is either required or provided. There is no central purpose for all parties.



SoS Authority

How do we handle collaboration and agreement when there is no overall director? Effective patterns for collaboration are needed, but are often difficult to recognise or establish. The defense sector tackles this with a focus on finding ways to balance the values & needs of constituent systems with those of the SoS. Other application domains tackle this through incentivizing constituent systems, creating an environment where they can meet their own goals whilst collaborating to support SoS goals.



SoS Principles

What are the key SoS thinking principles? Surveys of SoS practitioners have identified areas where basic principles are lacking. These include: lack of formalized SoS processes; lack of SoS success stories; and information about workflows. Much more research on SoS working contexts is needed to develop a body of recognized best practice.



Leadership

What are the roles & characteristics of effective SoS leaders? The increasingly complex collection of independent systems in an SoS typically straddles disciplines, application domains, organizations and even national boundaries, and each constituent system is capable of following their own interests and agenda. As a result, effective means of leadership are important. Structure and directorship usually found in SE projects is often absent for SoS, and other methods are needed to ensure coherence and direction.



Constituent Systems

How to integrate constituent systems? Each constituent system has its own agenda and goals, and can act autonomously. Some may be legacy systems not designed for SoS contexts, not easily adapted, resulting in interoperability challenges. Operating an SoS means finding means to coordinate, incentivize and manage multiple separate constituent systems, with separate working cultures, schedules, processes and working practices, as well as coping with technical challenges such as communications and data exchange. Mismatched assumptions and expectations are a real risk.

SoS Pain Points

What does a systems engineer need to know about SoS?
Many existing systems do play a role in an SoS, whether they are explicitly aware of this or not. Working in an SoS context brings a number of challenges, and it can help to be aware of these. Surveys conducted by the INCOSE SoS Working Group have identified "pain points" which are particularly associated with SoS by practising systems engineers (summarized by Judith Dahmann 2014).

[1] COMPASS project: <http://thecompassclub.org/>
[2] DANSE project: <http://danse-ip.eu/home/>
[3] INTO-CPS project: <http://projects.au.dk>

Autonomy, Interdependence & Emergence

How can system engineering address the complexities of SoS inter-dependencies and emergent behaviors? Identifying, uncoordinated evolution of constituent systems can lead to unanticipated emergent effects at the SoS level, often not observable until the SoS is simulated or tested. Complex dependencies are common between constituent systems at different stages of maturity, often not well understood or anticipated. The scale, diversity & independence in an SoS makes it difficult to produce models that can accurately predict SoS-level performance. Recent work has begun to address SoS and emergence, SoS uncertainty & complexity, and modelling & simulation – see, for example, [1, 2, 3].

INCOSE-TP-2018-003-01.0

CALIFORNIA HIGH-SPEED RAIL SYSTEM (CHSRS)

BRIEF INTRODUCTION



WHO WE ARE

WHAT WE DO

INSIGHTS

CAREERS

Investors ▾

News ▾

Contact us ▾



GLOBAL - ENGLISH ▾

FRANÇAIS

What We Do / Projects / CALIFORNIA HIGH SPEED RAIL



Source: <https://www.wsp.com/en-GL/projects/california-high-speed-rail>

CALIFORNIA HIGH SPEED RAIL

CALIFORNIA HIGH-SPEED RAIL SYSTEM

PROCUREMENT STRATEGY / CONTRACT PACKAGING



EXHIBIT X.X IMPLEMENTATION AND DELIVERY STRATEGY


OPERATOR



ROLLING STOCK



RAIL INFRASTRUCTURE



CIVIL WORKS



CEDAR VIADUCT



AVENUE 12




Source: 2018 Business Plan & 2019 Project Update Report to the California State Legislature.


Note: Revised Draft 2020 Business Plan available: https://hsr.ca.gov/docs/about/business_plans/2020_Business_Plan.pdf

CALIFORNIA HIGH-SPEED RAIL SYSTEM


CHSRS AS A SoS (PROGRAM OF PROJECTS)




CHSRS: PROGRAM DEVELOPMENT LIFE CYCLE




CHSRS: Use of Digital Threads (TRACEABILITY)



CHSRS: CONTRACT VS. SYSTEM CERTIFICATION



CHSRS: FOCUS OF THIS PRESENTATION





❖ Introduction

- Brief System of Systems (SoS) Overview
- California High-Speed Rail System (CHSRS) Program
- Use of Digital Threads in the CHSRS Program

❖ SoSE Challenges Faced

- Systems Engineering Challenges
- SoS Engineering Challenges


❖ SoSE Activities Performed

- Certification Strategy
- Step by Step Process Description

❖ Summary, Achieved Outcomes & Conclusion

SYSTEMS ENGINEERING CHALLENGES FACED

REQUIREMENTS QUANTITY






SYSTEMS ENGINEERING CHALLENGES FACED

NUMBER OF DESIGN/CONSTRUCTION ELEMENTS


RIVER CROSSING



UNDERCROSSING



TRENCH




VIADUCTS



225+ MAJOR
STRUCTURES


SYSTEMS ENGINEERING CHALLENGES FACED

NUMBER OF DESIGN/CONSTRUCTION ELEMENTS



SYSTEMS ENGINEERING CHALLENGES FACED

NUMBER OF DESIGN/CONSTRUCTION ELEMENTS (CONT'D)




SYSTEMS ENGINEERING CHALLENGES FACED


NUMBER OF DESIGN SUBMITTALS




Structural




Civil




Std. Const. Drwgs.



Geotechnical




Retaining Walls



SYSTEMS ENGINEERING CHALLENGES FACED

NUMBER OF DESIGN V&V REPORTS, SUBMITTAL CERTIFICATIONS



California High-Speed Train Design-Build Project
Construction Package 1

Structural

AVENUE 10 OVERHEAD
RFC DESIGN SUBMITTAL
DESIGN CHANGE NOTICE 081
VERIFICATION AND VALIDATION REPORT

March 2018

Agreement No. HSR 13-06

Prepared by:
Tutor Perini | ZACHRY | PARSONS, A Joint Venture

Table 2 - CIL

Derived Key	Appointed Key	Allocations	In Compliance with Contract Documents	Reference
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431

California High-Speed Train Design-Build Project
Construction Package 1

Civil

AVENUE 10 GRADE SEPARATION
READY FOR CONSTRUCTION PLANS
V&V FACT SHEET

April 2015

Agreement No. HSR 13-06

Prepared by:
Tutor Perini | ZACHRY | PARSONS, A Joint Venture

Table 2 - CIL

Derived Key	Appointed Key	Allocations	In Compliance with Contract Documents	Reference
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431

Certificates of Compliance

California High-Speed Train Design-Build Project
Construction Package 1

AVENUE 10 OVERHEAD
RFC DESIGN SUBMITTAL
DESIGN CHANGE NOTICE 081
VERIFICATION AND VALIDATION REPORT

March 2018

Agreement No. HSR 13-06

Prepared by:
Tutor Perini | ZACHRY | PARSONS, A Joint Venture

Std. Const. Drawgs.

California High-Speed Train Design-Build Project
Construction Package 1

OVERHEAD STANDARD CONSTRUCTION DRAWINGS
RFC DESIGN CHANGE NOTICE 098
VERIFICATION AND VALIDATION REPORT

January 2020

Agreement No. HSR 13-06

Prepared by:
Tutor Perini | ZACHRY | PARSONS, A Joint Venture

California High-Speed Train Design-Build Project
Construction Package 1

Geotechnical

GEOTECHNICAL ENGINEERING DESIGN REPORT (GEDR)
AVENUE 10 OVERHEAD (New)

April 2015

Agreement No. HSR 13-06

Prepared by:
Tutor Perini | ZACHRY | PARSONS, A Joint Venture

Table 2 - CIL

Derived Key	Appointed Key	Allocations	In Compliance with Contract Documents	Reference
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431

California High-Speed Train Design-Build Project
Construction Package 1

Retaining Walls

AVE 10 HST GRADE SEPARATION
MSE STRUCTURES
SPECIAL CONSTRUCTION SUBMITTAL
VERIFICATION AND VALIDATION REPORT

January 2018

Agreement No. HSR 13-06

Prepared by:
Tutor Perini | ZACHRY | PARSONS, A Joint Venture

Table 3 - CIL

Derived Key	Appointed Key	Allocations	In Compliance with Contract Documents	Reference
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431
Highway crossing at grade	N/A	N/A	Yes	SI-43100-431

SYSTEMS ENGINEERING CHALLENGES FACED

NUMBER OF SUBMITTAL RECORDS



Submittal Log			
Avenue 10			
Name	Title	SubmittalType	
17699	FCN 227 Avenue 10 HST Box Culvert	INFO	
17621	Avenue 10 OH Joint Seal	INFO	
17536	Avenue 10 Pavement Remediation Plan	INFO	
17469	Avenue 10 OH Construction SSCR	SONO	
15564	Easement Avenue	APPROVAL	
14656	Avenue 10 OH MSE Structure Pkg	APPROVAL	
14435	Avenue 10 HST Box Culvert RFC	APPROVAL	
11795	Avenue 10 HST Overhead SSCR	SONO	
11774	60% Avenue 10 HST Box Culvert	SONO	
11368	RFC Avenue 10 Overhead Design	APPROVAL	
10926	Avenue 10 Grade Separation Design	INFO	
10814	Avenue 10 Overhead GEDR	SONO	
10699	90 Perc Dsgn Avenue 10 OH	SONO	
10065	Avenue 8, Avenue 9, and Avenue 10	3RDPARTY	

Safety & Security Certification Report

Fourth Revision			
004	PCM_TPZP__03882_COF_Relocations	PCM_TPZP__03882_COF_Relocations.pdf	
004	Signed Plan Set	2018May14_DCN081_Avenue_10_OH_Plans_Signed	2018May14_DCN081_Avenue_10_OH_Plans_Signed.pdf
004	CHSRA_trans_05027 Signed Plans DCN-081 Avenue 10 OH Design SW04.13.00-019-4	CHSRA_trans_05027_Signed_Plans_DCN_081_Avenue_10_OH_Design_SW04_13_00_019_4	CHSRA_trans_05027_Signed_Plans_DCN_081_Avenue_10_OH_Design_SW04_13_00_019_4.pdf
004	Authority's Response	SW04_13_00_019_4_RFC_Ave_10_OH_Design_Response	SW04_13_00_019_4_RFC_Ave_10_OH_Design_Response.pdf
004	DCN081 Avenue 10 Overhead Design	2017Oct31_DCN081_Ave_10_OH_DCN_Form	2017Oct31_DCN081_Ave_10_OH_DCN_Form.pdf
004	DCN081 Avenue 10 Overhead Design	2017Oct31_DCN081_Ave_10_OH_ISC_Statement_Resolution	2017Oct31_DCN081_Ave_10_OH_ISC_Statement_Resolution.pdf
004	DCN081 Avenue 10 Overhead Design	2017Oct31_DCN081_Ave_10_OH_ISC_Book	2017Oct31_DCN081_Ave_10_OH_ISC_Book.pdf
004	DCN081 Avenue 10 Overhead Design	2017Oct31_DCN081_Ave_10_OH_GEDR	2017Oct31_DCN081_Ave_10_OH_GEDR.pdf
004	Submittal Cover Page	2018May16_SL_Cover_SW041300_019_4_DCN081_Ave_10_OH_Design	2018May16_SL_Cover_SW041300_019_4_DCN081_Ave_10_OH_Design.pdf
004	DCN081 Avenue 10 Overhead Design	2018May14_DCN081_Ave_10_OH_CHSRA_Response	2018May14_DCN081_Ave_10_OH_CHSRA_Response.pdf
004	DCN081 Avenue 10 Overhead Design	2018May14_DCN081_Ave_10_OH_ICE_Cert	2018May14_DCN081_Ave_10_OH_ICE_Cert.pdf
004	DCN081 Avenue 10 Overhead Design	2018May14_DCN081_Ave_10_OH_Plans	2018May14_DCN081_Ave_10_OH_Plans.pdf
004	DCN081 Avenue 10 Overhead Design	2018May14_DCN081_Ave_10_OH_QA_Cert1386	2018May14_DCN081_Ave_10_OH_QA_Cert1386.pdf
000	RFC_Avenue_10_Overhead_Design	2015Dec03_Ave_10_OH_RFC_VV_Cert_Compliance	2015Dec03_Ave_10_OH_RFC_VV_Cert_Compliance.pdf
000	RFC_Avenue_10_Overhead_Design	2015Dec03_Ave_10_OH_StcrtRpt_ICE_Assessment	2015Dec03_Ave_10_OH_StcrtRpt_ICE_Assessment.pdf

Design Change Notice (DCN)

Plans (Design Drawings)

Verification & Validation, Submittal Certification

SYSTEMS ENGINEERING CHALLENGES FACED

ALLOCATED REQUIREMENTS & OBJECTIVE EVIDENCE



Submittal Log		
Avenue 10		
Name	Title	SubmittalType
17699	FCN 227 Avenue 10 HST Box Culvert	INFO
17621	Avenue 10 OH Joint Seal	INFO
17536	Avenue 10 Pavement Remediation Plan	INFO
17469	Avenue 10 OH Construction SSCR	SONO
15564	Easement T1-091 (AT&T) – Avenue 10	APPROVAL
14656	Avenue 10 OH MSE Structure Pkg	APPROVAL
14435	Avenue 10 HST Box Culvert RFC	APPROVAL
11795	Avenue 10 HST Overhead SSCR	SONO
11774	60% Avenue 10 HST Box Culvert	SONO
11368	RFC Avenue 10 Overhead Design	APPROVAL
10926	Avenue 10 Grade Separation Design	INFO
10814	Avenue 10 Overhead GEDR	SONO
10699	90 Perc Dsgn Avenue 10 OH	SONO
10065	Avenue 8, Avenue 9, and Avenue 10	3RDPARTY

000 RFC_Avenue_10_Overhead_Design 2015Dec03_Ave_10_OH_RFC_VV_Cert_Compliance

000 RFC_Avenue_10_Overhead_Design 2015Dec03_Ave_10_OH_StartRpt_ICE_Assessment

61 - 81

81 Files

Verification & Validation, Submittal Certification

California High-Speed Train Project Construction Package 1

ID	Doc. ID	DOORS TCR #	Document Section	Technical Contract Requirement
86.	Design Criteria	CDPt22SR569	22.5 Overhead	
87.	Design Criteria	CDPt03SR1963	3.3.1 Vertical Clearances	Minimum vertical clearances should be laterally from the centerline of the mo
88.	Design Criteria	CDPt03SR24	3.3.1 Vertical Clearances	Minimum vertical clearances shall be of rail (TOR).
89.	Design Criteria	CDPt03SR46	3.3.2 Horizontal Clearances	Minimum horizontal clearances shall centerline (TCL) of the closest HST tra cleared.
90.	Scope of Work	SOW609	4.2.2 Review of Environmental Documents	Compliance with all Final Environment demonstrated through preparation of reports, to be submitted with each de
91.	Design Criteria	CDPt06SR55	6.3.2 Protection Against Intrusion of Highway Vehicles over the HST Operating Infrastructure	The overhead structure shall be design railing with sufficient strength to with
92.	Design Criteria	CDPt06SR56	6.3.2 Protection Against Intrusion of Highway Vehicles over the HST Operating Infrastructure	The vehicular railing shall extend to the feet beyond the end of the overhead taper to redirect vehicles that may tra embankment and into the Authority's

Contractor V&V Report (Including Requirements Verification Traceability Matrix [RVTM])

California High-Speed Train Design-Build Project Construction Package 1

Avenue 10 Overhead RFC Design Submittal Verification and Validation Report

August 2015

Agreement No. HSR 13-06

Prepared by:

Objective Evidence (Reference and RM Tool Traces)

In Compliance with Contract Documents	Reference
Yes	Overhead Standard Construction Drawings ST-K5020-STD, ST-K5021-STD, ST-5022-STD
Yes	ST-K1100-A10, Calcs. Section 2.3
Yes	ST-K1100-A10, Calcs. Section 2.3
Yes	ST-K1100-A10
Yes	Environmental Certification
Yes	ST-K1100-A10, ST-K3350-A10, Calcs. Section 3.2.2
Yes	ST-K1100-A10

Allocated Requirements (Technical Contract Requirements [TCR])


Tutor Perini ZACHRY PARSONS

SYSTEMS ENGINEERING CHALLENGES FACED

CONSTRUCTION CERTIFICATION: QUALITY MILESTONE (DATA PACK, QMDP)



Submittal Log		
Avenue 10		
Name	Title	SubmittalType
17699	FCN 227 Avenue 10 HST Box Culvert	INFO
17621	Avenue 10 OH Joint Seal	INFO
17536	Avenue 10 Pavement Remediation Plan	INFO
17469	Avenue 10 OH Construction SSCR	SONO
15564	Easement T1-091 (AT&T) – Avenue 10	APPROVAL
14656	Avenue 10 OH MSE Structure Pkg	APPROVAL
14435	Avenue 10 HST Box Culvert RFC	APPROVAL
11795	Avenue 10 HST Overhead SSCR	SONO
11774	60% Avenue 10 HST Box Culvert	SONO
11368	RFC Avenue 10 Overhead Design	APPROVAL
10926	Avenue 10 Grade Separation Design	INFO
10814	Avenue 10 Overhead GEDR	SONO
10699	90 Perc Dsgn Avenue 10 OH	SONO
10065	Avenue 8, Avenue 9, and Avenue 10	3RDPARTY



SoS ENGINEERING CHALLENGES FACED

INDEPENDENTLY MANAGED (& OPERATED) PROJECTS (CONSTITUENT SYS.)



Milestones & the Field Engineers responsible for the

GDW01 MADERA COUNTY GUIDEWAY - Litto
GDW02 SJRV TO FRESNO TRENCH GUIDEWAY - Litto
GDW03 FRESNO TRENCH TO AMERICAN AVENUE GUIDEWAY - Litto

NE01 ROAD 26 - Katrina
NE02 SCHMIDT CREEK HST - Katrina
NE03 SCHMIDT CREEK CULVERT BOX - Katrina
NE04 WILDLIFE CROSSING MP167.4 - Katrina
NE05 ROAD 27 - Katrina
NE06 AVE 17 - Katrina

STR01 FRESNO RIVER VIADUCT (FRV) - Gavin
STR02 AVENUE 15-1/2 OH - Katrina
STR03 AVENUE 15 OH - Katrina
STR04 COTTONWOOD CREEK BR - Katrina
STR05 AVENUE 12 HST OH - Katrina
STR06 AVENUE 12 BNSF OH - Katrina
STR07 AVENUE 11 OH - Katrina

STR08 AVENUE 10 OH - Katrina
STR09 AVENUE 9 OH - Katrina
STR10 AVENUE 8 OH - Katrina
STR11 AVENUE 7 OH - Katrina

STR12 SAN JOAQUIN RIVER VIADUCT (SJRV) - Doug
STR12A W HERNDON AVE HST OP - Doug
STR12B W HERNDON AVE UPRR OP - Doug

STR13 SHAW AVENUE OH - Sri
STR14 MCKINLEY AVENUE OH - Sri
STR15 OLIVE AVENUE OH - Sri
STR16 BELMONT AVENUE OH - Sri
STR17 FRESNO TRENCH - Tyler B
STR18 TUOLUMNE STREET OH - Matt K


STR19 FRESNO STREET UP - Gavin
STR20 TULARE STREET UP - Gavin
STR21 VENTURA AVENUE UP - Gavin
STR22 E CHURCH AVENUE HST - Gavin
STR22A E CHURCH AVENUE BNSF OH - Gavin
STR23 JENSEN TRENCH - Tyler B

STR24B E MUSCAT AVE HST - Gavin
STR25 CENTRAL AVENUE OH - Gavin
STR26 AMERICAN AVENUE OH - Gavin

3RDP001 AT&T - Juan
3RDP002 PG&E - Bianca
3RDP003 CITY OF FRESNO - Bennie
3RDP004 COUNTY OF FRESNO - Bennie
3RDP005 COUNTY OF MADERA - Bennie
3RDP006 UPRR - Addison
3RDP007 BNSF - Addison
3RDP008 CALTRANS - Bennie
3RDP009 MADERA IRRIGATION DISTRICT - Greg
3RDP010 FRESNO IRRIGATION DISTRICT - Greg
3RDP011 FMFCD - Greg
3RDP012 KINDER MORGAN - Addison
3RDP013 LEVE III - Addison
3RDP014 COMCAST - Addison
3RDP015 SPRINT - Addison
3RDP016 TW TELECOM - Addison
3RDP017 TIME WARNER - Addison
3RDP018 QWEST - Addison
3RDP019 CVIN - Addison
3RDP020 SEBASTIAN KERMAN TELECOM - Addison
3RDP021 MCI - Addison
3RDP022 SIERRA TELEPHONE - Addison

List of Quality Milestone
Data Packs (QMDPs)

California High-Speed Train Project CP1 Key Map



SoS ENGINEERING CHALLENGES FACED

INDEPENDENTLY MANAGED (& OPERATED) PROJECTS (CONT'D)




QUALITY MILESTONE ID			STRUCTURES	STATIONING	QUALITY MILESTONE ID				
R-CIVIL	S-RDWAY	H-TRACK			T-CIVIL TRACK				
RDWY	STRUC	STRUC			NORTH/SOUTH	BNSF			
Management Segment 1 (STA 587+30 to 1595+00)									
			1R-01	Start Segment 1	587+30	S1TN1	5000 ft		
S1R1	S1S1			Lincoln (Cul-de-Sac)	630+30	ROW 1	0.95 mi		
				End ROW 2	636+90	ROW 2			
				Start ROW 3	636+90	S1TN3	5278 ft		
S1R3	S1S3		1R-02	Adams OC	683+06	ROW 3	1.01 mi		
				End ROW 4	689+68	ROW 4			
				Start ROW 5	689+68	S1TN5			
				Start BNSF	707+00	ROW 5	5305 ft		
S1R5	S1S5		1R-03	South OC	735+89	ROW 6	1 mi	S1TBN1	16200 ft 3.06 mi
				End ROW 6	742+73				
				Start ROW 7	742+73	S1TN7	5261 ft		
S1R7	S1S7		1R-04	Manning OC	788+82	ROW 7	0.996 mi		
	*S1S8		1R-05	Manning Change OC	788+83	ROW 8			
				End ROW 8	795+34				
				Start ROW 9	795+34	S1TN9	8482 ft		
				End BNSF	869+00	ROW 9	1.61 mi		
				End ROW 9	880+16				
S1R9	S1S9		1R-06	Floral OC	880+16	S1TN11	4209 ft		
				Start ROW 10	880+16	ROW 10	0.8 mi		
				End ROW 10	922+25				
				Start ROW 11	922+25	S1TN13			
				Start BNSF	932+00	ROW 11	6844 ft		
S1R11	S1S11		1R-07	Nebraska OC	953+20		1.296 mi		
				End ROW11	990+69				
				Start ROW12	990+69	S1TN15		S1TBN2	13000 ft 2.46 mi
S1R13	S1S13		1R-08	Mountain View OC	1004+61	ROW 12	8431 ft		
				End BNSF	1062+00	ROW 13	1.6 mi		
				End North Track	1075+00				
				Start South Track	1075+00				
		S1H1	1H-01	Conejo Ave AS	1114+48				
					1134+25	S1TS1	10185 ft		
S1R14		S1H3	1H-02	Peach Ave BR	1146+23	ROW 13	1.93 mi		
					1149+29			CP2-3	
				End ROW 13	1176+85				
				Start ROW 14	1176+85				
S1R15				Clarkson / Minnewawa	1175+00	S1TS3	5782 ft		
					1202+00	ROW 14	1.1 mi		
				REMOVED Clovis OC STA 1221+78					
				End ROW 14	1234+67				
				Start ROW 15	1234+67	S1TS5			
S1R17	S1S15		1R-10	Elkhorn OC	1247+36	ROW 15	8026 ft		
S1R19	S1S17		1R-11	Fowler OC	1276+61	ROW 16	1.52 mi		
				End ROW 16	1314+93				
				Start ROW 17	1314+93	S1TS7	8007 ft		

#	Activity ID	QMDP #	Activity Name	Stationing
1	MIL_1285	QMDP 01	EOP to County Line	14769+23 - 14822+00
2	MIL_1290	QMDP 02	County Line to S Scofield	14822+00 - 14877+00
3	MIL_1295	QMDP 03	S Scofield to Garces Abut1	14877+00 - 14931+21
4	MIL_1145	QMDP 04	Garces Hwy Underpass	14931+31 - 14932+23
5	MIL_1300	QMDP 05	Garces Abut. 2 to Woollomes Ave	14932+23 - 14989+50
6	MIL_1305	QMDP 06	Woollomes Ave to Pump Station	14989+50 - 15055+00
7	MIL_1310	QMDP 07	Pump Station to S. Magnolia	15055+00 - 15096+50
8	MIL_1315	QMDP 08	S. Magnolia to Pond Rd. Abut. #1	15096+50 - 15119+73
9	MIL_1115	QMDP 09	Pond Rd Underpass	15119+72 - 15120+94
10	MIL_1320	QMDP 10	Pond Rd. Abut. 2 to Peterson Rd. Abut. 1	15120+94 - 15182+09
11	MIL_1155	QMDP 11	Peterson Rd Underpass	15182+09 - 15183+11
12	MIL_1325	QMDP 12	Peterson Rd. Abut. 1 to Elmo Hwy	15183+12 - 15242+00
13	MIL_1330	QMDP 13	Elmo Hwy to Sherwood Ave	15242+00 - 15294+50
14	MIL_1335	QMDP 14	Sherwood Ave to Poso Creek Abut. 1	15294+50 - 15329+88
15	MIL_1105	QMDP 15	Poso Creek Overpass	15329+89 - 15332+27
16	MIL_1340	QMDP 16	Poso Creek Abut. 1 to Taussig Ave.	15332+27 - 15375+50
17	MIL_1345	QMDP 17	Taussig Ave to Canal 9-22	15375+50 - 15426+88
18	MIL_1350	QMDP 18	Canal 9-22 to McCombs Ave.	15426+88 - 15505+00
19	MIL_1185	QMDP 19	McCombs Ave Overpass	15501+55 - 15501+95
20	CP4	QMDP 20	McCombs Ave.to SR-46 Abut. 1	15509+00 - 15560+89
21	CP4	QMDP 21	SR 46 Underpass	15560+89 - 15562+12
22	MIL_1360	QMDP 22	SR-46 Abut. 1 to Pedestrian Underpass	15563+00 - 15587+00
23	MIL_1085	QMDP 23	HST Pedestrian Underpass	15588+25 - 15590+25
24	MIL_1365	QMDP 24	Pedestrian Underpass to Poso Ave	15590+00 - 15614+00
25	MIL_1195	QMDP 25	Poso Ave Underpass	15613+83 - 15614+43
26	MIL_1370	QMDP 26	Poso Ave to Wasco Viaduct Abut. 1	15614+00 - 15660+00
27	MIL_1270	QMDP 27	Wasco Viaduct	15660+20 - 15679+73

SoS ENGINEERING CHALLENGES FACED

CERTIFICATION APPROACH: PUTTING IT ALL BACK TOGETHER



SOURCE/CREDIT:
[HTTPS://GARAGESIMEONE.CH/P
ORTFOLIO-VIEW/ORIGINALTEILE/](https://garagesimeone.ch/portfolio-view/originalteile/)



❖ Introduction

- Brief System of Systems (SoS) Overview
- California High-Speed Rail System (CHSRS) Program
- Use of Digital Threads in the CHSRS Program

❖ SoSE Challenges Faced

- Systems Engineering Challenges
- SoS Engineering Challenges



❖ SoSE Activities Performed

- Certification Strategy
- Step by Step Process Description

❖ Summary, Achieved Outcomes & Conclusion

SoSE ACTIVITIES PERFORMED

HIGH-LEVEL VERIFICATION, VALIDATION & CERTIFICATION STRATEGY



SoSE ACTIVITIES PERFORMED

VERIFICATION & VALIDATION APPROACH



SYSTEMS ENGINEERING CHALLENGES FACED

REQUIREMENTS QUANTITY

Contract Documents

- CONSTRUCTION PACKAGE 1 (HSR 13-06)
- EXECUTED AGREEMENT: HSR 13-06
- General Provisions: 234 Pages, 1,334 Staff Statements
- Scope of Work: 67 Pages, 417 Staff Statements
- Design Criteria Manual: 1,219 Pages, 7,951 Staff Statements
- Third Party Agreements: 434 Pages, 2,214 Staff Statements
- Standard Specifications: 434 Pages, 2,214 Staff Statements

SYSTEMS ENGINEERING CHALLENGES FACED

NUMBER OF DESIGN/CONSTRUCTION ELEMENTS

Types

- RIVER CROSSING
- UNDERCROSSING
- VIADUCT
- 225+ MAJOR STRUCTURES

SYSTEMS ENGINEERING CHALLENGES FACED

NUMBER OF DESIGN SUBMITTALS

Sites

- Structural
- Geotechnical
- Retention

SYSTEMS ENGINEERING CHALLENGES FACED

ALLOCATED REQUIREMENTS & OBJECTIVE EVIDENCE

Submittals

- Contractor V&V Report (including Requirements, Verification, Traceability Matrix (RVTM))
- California High-Speed Train Design-Build Project
- August 2015 Agreement No. HSR 13-06


Contract Documents	TCR Attribute	Techn. Contract Requirements	Alloc. Attribute	General / Typical Requirements	Site Alloc. Attribute	Site-Specific Requirements	Submit Alloc. Attribute	Submittal-Specific Requirements (RVTM)	Objective Evidence
Contract Document #1		Contract Document #1	RM Tool Attributes
...			
General Provisions		General Provisions	EW	Earthworks Requirements	Earthworks #1	Earthworks #1 Requirements	Submittal #1	Submittal Req. #1	Submittal #1
Scope of Work		Scope of Work	AS	...	Aerial Str. #1	Earthworks #n Requirements	Submittal #2	Submittal Req. #2	Submittal #2
Design Criteria Manual		Design Criteria Manual	TR	Trench Structure Requirements	Trench Str. #1
...		...	OH	Roadway Overhead Requirements	Overhead #1	Overhead #1 Requirements	Submittal #n
Contract		Contract		Overhead #n Requirements	Submittal #n

SoSE ACTIVITIES PERFORMED

VERIFICATION & VALIDATION APPROACH: 6 KEY STEPS



SYSTEMS ENGINEERING CHALLENGES FACED REQUIREMENTS QUANTITY



Contract

SYSTEMS ENGINEERING CHALLENGES FACED NUMBER OF DESIGN/CONSTRUCTION ELEMENTS




Types

SYSTEMS ENGINEERING CHALLENGES FACED NUMBER OF DESIGN SUBMITTALS




Sites

SYSTEMS ENGINEERING CHALLENGES FACED ALLOCATED REQUIREMENTS & OBJECTIVE EVIDENCE



Submittals




SoSE ACTIVITIES PERFORMED

PERFORMANCE REQ. EXAMPLE: STEP 1 – CONTRACT REQUIREMENTS



SYSTEMS ENGINEERING CHALLENGES FACED REQUIREMENTS QUANTITY



Contract

Contract Documents

TCR Attribute

Contract Document #1

...

General Provisions

Scope of Work

Design Criteria Manual

...

Contract

Yes
No

- 15 Dispatch and service of the different users on a shared track segment will be governed by an agreement between operators in the segment.
- 16
- 17 Dispatch and service will be performed by the shared control facility operating the shared track segment under rules described into a host/tenant agreement.
- 18
- 19 The System in the shared-use corridor shall safely accommodate maintenance activities without disruption to daily operations.
- 20
- 21 **2.2.3.5 Policy Consideration**
- 22 The Authority will establish new policies and/or upgrade the Authority policies that were established for dedicated high-speed operation to cover operation conditions introduced for the operation of high-speed rail trains in the blended system corridor.
- 23
- 24
- 25 Attachment D presents a summary of the policies that require revision and identifies new policies that may be required to support blended operation within the corridor.
- 26
- 27 **2.2.3.6 Operating and Design Speed**
- 28 The CHSR System operating speed shall be 220 mph.
- 29 In areas of shared-use track, operating speed shall be 110 mph, including the following:
- 30
- 31 Peninsula Corridor from San Francisco to Gilroy
 - 32 Burbank to Anaheim project section in Phase 1 of the project
 - 33 Los Angeles to San Diego in the Phase 2 of the project
- 34 The System design speed shall be 250 mph.
- 35 In areas of shared-use track, design speed shall be as follows:
- 36 Peninsula Corridor from San Francisco to Gilroy: 110 mph
 - 37 Burbank to Anaheim project section in Phase 1 of the project: 125 mph
 - 38 Los Angeles to San Diego in Phase 2 of the project: 125 mph
- 39 The CHSR System design shall incorporate the needs for a testing speed of at least 110 percent of the operating speed.



Chapter 2 – Basis of Design

ID	08/02/2021 Rev. 4.5 - BOD	_TCR
18	2 Basis of Design	Heading
20	2.2 Design Criteria Elements	Heading
23	2.2.3 Train Operation	Heading
29	2.2.3.6 Operating and Design Speed	Heading
30	The System design speed shall be 250 mph.	TCR

Site Alloc. Attribute	Site-Specific Requirements	Submit Alloc. Attribute	Submittal-Specific Requirements (RVTM)	Objective Evidence
...
Earthworks #1	Earthworks #1 Requirements	Submittal #1	Submittal Req. #1	Submittal #1
...	...	Submittal #2	Submittal Req. #2	Submittal #2
...
...	...	Submittal #n
...
...
Overhead #1	Overhead #1 Requirements	Submittal #1	Submittal Req. #1	Submittal #1
...	...	Submittal #2	Submittal Req. #2	Submittal #2
...
...	Overhead #n Requirements	Submittal #n

SoSE ACTIVITIES PERFORMED

PERFORMANCE REQ. EXAMPLE: STEP 2 – TECHNICAL CONTRACT REQS.



ID	Technical Contract Requirements (TCR)	ABL
TCR.1	1 General Provisions	---
TCR.45	1.44 Sustainability	---
TCR.47	1.44.2 Requirements	---
TCR.48	k. The Contractor shall provide Environmental Product Declarations from its suppliers and manufacturers for concrete mix designs used in elements of the Project, including pre-cast and cast-in-place concrete, and all steel. The Contractor shall enter and upload Environmental Product Declarations in EMMA for concrete and steel.	PW
TCR.49	2 Scope of Work	---
TCR.53	2.4 PROJECT SCOPE OF WORK	---
TCR.64	2.4.9 Design Reports	---
TCR.66	2.4.9.2 Hydrology and Hydraulic Reports	---
TCR.67	Contractor shall prepare Hydrology and Hydraulics Reports to support the drainage design of the full build-out of the CHSR trackway, as well as the temporary drainage system for the interim condition.	PW
TCR.68	Contractor shall contact and coordinate with State (NOAA Atlas 14, Volume 6, Version 2) and local (City of Bakersfield - Subdivision & Engineering Design Manual, Division 7) jurisdictions to obtain necessary information for preparation of its reports.	PW
TCR.69	3 Design Criteria	---
TCR.71	3.2 Basis of Design	---
TCR.73	3.2.2 Design Criteria Elements	---
TCR.76	3.2.2.3 Train Operation	---
TCR.82	3.2.2.3.6 Operating and Design Speed	---
TCR.83	The System design speed shall be 250 mph.	PW EW AS
TCR.87	3.6 Reliability, Availability, and Maintainability	---
TCR.256	3.6.2 Design Criteria Elements	---
TCR.257	3.6.2.1 Reliability (Availability)	---

040 Design Analyses/050 ABL/010 SYS/010 PW-TCR >

040 Design Analyses/050 ABL/020 SUB-SYS/020 EW-TCR >

040 Design Analyses/050 ABL/020 SUB-SYS/030 AS-TCR >

Digital Threads

SoSE ACTIVITIES PERFORMED

PERFORMANCE REQ. EXAMPLE: STEP 3 – TYPICAL (EW) REQUIREMENTS



HSR Earthworks (Type) Applicable (Subsets) TCRs

Sites

3 Design Criteria

3.2 Basis of Design

3.2.2 Design Criteria Elements

3.2.2.3 Train Operation

3.2.2.3.6 Operating and Design Speed

The System design speed shall be 250 mph.

Allocations to Individual Sites

EW-EMB-SITE01
EW-CUT-SITE02

3.29 Geotechnical

3.29.2 Design Criteria Elements

3.29.2.6 Earthworks

3.29.2.6.1 Earthwork Materials

3.29.2.6.1.3 HSR Prepared Subgrade

The required minimum thickness of the Prepared Subgrade is as follows:

- Ballasted track on embankment or in a cut: 14 inches.
- Slab track on embankment, where embankment height is equal to or greater than 6.5 feet (as measured from the top of the prepared subgrade at the side edge of the embankment to the existing ground surface): 6.5 feet.

EW-EMB-SITE01
EW-CUT-SITE02

5 Supplemental Contract Requirements

5.2 Engineering and Construction UPRR Agreement

5.2.3 Design and Construction

(d) Except as may be permitted in UPRR-approved Final Plans, at any location where the centerline of CHSRA tracks will be designed to be 102 feet or closer to UPRR's property, CHSRA must design, construct, and maintain intrusion barriers between the CHSRA tracks and UPRR's property. UPRR acknowledges that CHSRA will seek many such exceptions when it reasonably believes that approval of an exception would not have an adverse impact on safe or efficient operations.

EW-EMB-SITE01

Techn. Contract Requirements

Alloc. Attribute

General / Typical Requirements

...

...

EW

Earthworks Requirements

AS

Aerial Structure Requirements

TR

Trench Structure Requirements



OH

Roadway Overhead Requirements

Technical Contract Requirements (TCR)

SoSE ACTIVITIES PERFORMED

PERFORMANCE REQ. EXAMPLE: STEP 4 – SITE-SPECIFIC REQUIREMENTS



General / Typical Requirements	Site Alloc. Attribute	Site-Specific Requirements
...
Earthworks Requirements	Earthworks #1	Earthwork Requirements
Aerial Structure Requirements	Aerial Str. #1	Earthwork Requirements
Trench Structure Requirements	Trench Str. #1	...
Roadway Overhead Requirements	Overhead #1	Overhead Requirements
...	...	Overhead Requirements

HSR Earthworks #1 (Site-Specific Applicable (Subsets) TCRs)		Submittals
1 Design Criteria		---
1.2 Basis of Design		
1.2.2 Design Criteria Elements		
1.2.2.3 Train Operation		Allocations to Submittals
1.2.2.3.6 Operating and Design Speed		
The System design speed shall be 250 mph.		EW-DES-60% EW-DES-90% EW-DES-RFC EW-DES-DCN
1.29 Geotechnical		
1.29.2 Design Criteria Elements		
1.29.2.6 Earthworks		
1.29.2.6.1 Earthwork Materials		
1.29.2.6.1.3 HSR Prepared Subgrade		
The required minimum thickness of the Prepared Subgrade is as follows:		
<ul style="list-style-type: none">Ballasted track on embankment or in a cut: 14 inches.Slab track on embankment, where embankment height is equal to or greater than 6.5 feet (as measured from the top of the prepared subgrade at the side edge of the embankment to the existing ground surface): 6.5 feet.		EW-DES-60% EW-DES-90% EW-DES-RFC EW-DES-DCN
3 Supplemental Contract Requirements		
3.2 Engineering and Construction UPRR Agreement		
3.2.3 Design and Construction		
(d) Except as may be permitted in UPRR-approved Final Plans, at any location where the centerline of CHSRA tracks will be designed to be 102 feet or closer to UPRR's property, CHSRA must design, construct, and maintain intrusion barriers between the CHSRA tracks and UPRR's property. UPRR acknowledges that CHSRA will seek many such exceptions when it reasonably believes that approval of an exception would not have an adverse impact on safe or efficient operations.		EW-DES-60% EW-DES-90% EW-DES-RFC EW-DES-DCN

PERFORMANCE REQ. EXAMPLE: STEP 5 – SUBMITTAL SPECIFIC REQS.



Objective Evidence

TRACK GUIDEWAY - HORIZONTAL ALIG

TYPICAL TRACK SECTION - SHEET 1 OF 1

TYPICAL TRACK SECTION - SHEET 2 OF 2

TYPICAL TRACK SECTION - SHEET 3 OF 3

TYPICAL TRACK SECTION - SHEET 4 OF 4

TYPICAL TRACK SECTION - SHEET 5 OF 5

TYPICAL TRACK SECTION - SHEET 6 OF 6

TYPICAL TRACK SECTION - SHEET 7 OF 10

TYPICAL TRACK SECTION - SHEET 8 OF 10

TYPICAL TRACK SECTION - SHEET 8 OF 10
TYPICAL TRACK SECTION - SHEET 8 OF 10

TYPICAL TRACK SECTION - SHEET 10 OF 10

TYPICAL TRACK SECTION - SHEET 14 OF 14

TYPICAL TRACK SECTION - SHEET 11 OF 12

TYPICAL TRACK SECTION - SHEET 12 OF 12

TYPICAL TRACK SECTION - SHEET 13 OF 14

TYPICAL TRACK SECTION - SHEET 14 OF 15

SoSE ACTIVITIES PERFORMED



PERFORMANCE REQ. EXAMPLE: STEP 6 – SUBMITTAL LOG & REPOSITORY

	Subm-ID	Subm-Name	Drwg-ID	Drawing Name	Drwg-Rev
1 Design Criteria					
1.2 Basis of Design					
1.2.2 Design Criteria Elements					
1.2.2.3 Train Operation					
1.2.2.3.6 Operating and Design Speed					
The System design speed shall be 250 mph.	14060	GDW01	TT-D0001	TRACK GUIDEWAY - HORIZONTAL ALIGNMENT DATA TABLE	0
			TT-E6001	TRACK CHART - SHEET 1 OF 13	0
			TT-E6002	TRACK CHART - SHEET 2 OF 13	0
			TT-E6003	TRACK CHART - SHEET 3 OF 13	0
			TT-E6004	TRACK CHART - SHEET 4 OF 13	0
1.29 Geotechnical					
1.29.2 Design Criteria Elements					
1.29.2.6 Earthworks					

Submittal

Reference to Objective Evidence

Drawing #	Drawing Name
GE-D0001	COVER SHEET
...	...
TT-D0001	TRACK GUIDEWAY - HORIZONTAL ALIGNMENT DATA TABLE
TT-E6001	TRACK CHART - SHEET 1 OF 13
TT-E6002	TRACK CHART - SHEET 2 OF 13
TT-E6003	TRACK CHART - SHEET 3 OF 13
TT-E6004	TRACK CHART - SHEET 4 OF 13
TT-D3001	TYPICAL TRACK SECTION - SHEET 1 OF 14
TT-D3002	TYPICAL TRACK SECTION - SHEET 2 OF 14
TT-D3003	TYPICAL TRACK SECTION - SHEET 3 OF 14
TT-D3004	TYPICAL TRACK SECTION - SHEET 4 OF 14
TT-D3005	TYPICAL TRACK SECTION - SHEET 5 OF 14
TT-D3006	TYPICAL TRACK SECTION - SHEET 6 OF 14
TT-D3007	TYPICAL TRACK SECTION - SHEET 7 OF 14
TT-D3008	TYPICAL TRACK SECTION - SHEET 8 OF 14
TT-D3009	TYPICAL TRACK SECTION - SHEET 9 OF 14
	TYPICAL TRACK SECTION - SHEET 10 OF 14
	TYPICAL TRACK SECTION - SHEET 11 OF 14
	TYPICAL TRACK SECTION - SHEET 12 OF 14
TT-D3013	TYPICAL TRACK SECTION - SHEET 13 OF 14

Submittal Log	Subm-ID	Sub Name (Short)	Sub Name (Full)
1 Submittal Log			
1.3 HSR Earthworks			
1.3.1 EW-EMB-SITE01	---	---	---
RFC	14060	GDW01	Guideway Package 1, RFC
1.4 HSR Aerial Structure			
1.4.1 AS-VD-SITE01	---	---	---
RFC	11893	FRV, RFC	Fresno River Viaduct, RFC
Drawings			
V&V Submittal			
Certification of Compliance			

CP2-3, CP4: Submittal Log


New CPx: Submittal Repository
(Example: Drawing List)

SoSE ACTIVITIES PERFORMED


PERFORMANCE REQ. EXAMPLE: STEP 6 – OBJECTIVE EVIDENCE

Drawing #	Drawing Name	Rev	Page #
GE-D0001	COVER SHEET	0	1
...	...		
TT-D0001	TRACK GUIDEWAY - HORIZONTAL ALIGNMENT DATA TABLE	0	8
TT-E6001	TRACK CHART - SHEET 1 OF 13	0	9
TT-E6002	TRACK CHART - SHEET 2 OF 13	0	10
TT-E6003	TRACK CHART - SHEET 3 OF 13	0	11

Digital Thread



Page 9 of 340



Drawing TT-E6001

Tutor Perini | ZACHRY | PARSONS, A Joint Venture

Verification and Validation Certification of Compliance

Submittal Identification	
Project Name:	California High Speed Rail Train Project, CP1
Project Number:	HSR13-06
Document Title:	Guideway Station 9772+35.08 to 10304+00.00 Ready for Construction
Date:	09/11/2017

Submittal Verification Status	
Prepared By:	
Verified By:	
Signed off by V & V Manager:	
Date:	

The TP2P V&V team has reviewed and assessed the contract documents including Attachment 8 for all Ready for Construction (RFC) submittals.

The TP2P V&V team confirms that, with the inclusion of the Ready for Construction Certification, all comments received during the 90% Design Submittal review, Submittal reference SIV04.11.03-034 have been satisfactorily resolved and verified by the Design Lead and are represented in the RFC Submittal herein. The submittal is complete, contains the required documents inclusive of manuals, reports, drawings, procedures, policies, permits, and agreements to demonstrate compliance of this RFC submittal with the Technical Contract Requirements.


TP2P therefore self-certifies the submittal for Guideway Station 9772+35.08 to 10304+00.00 Ready for Construction to be compliant with Contract Requirements and fitness for purpose.

Submittal Certification of Compliance (CoC)

SoSE ACTIVITIES PERFORMED

VERIFICATION, VALIDATION & CERTIFICATION

CHSRs: FOCUS OF THIS PRESENTATION



Tutor Perini | ZACHRY | PARSONS, A Joint Venture

Verification and Validation Certification of Compliance

Submittal Identification	
Project Name:	California High Speed Rail Train Project, CP1
Project Number:	HSR13.06
Document Title:	Guideway Station 9772+35.08 to 10304+00.00 Ready for Construction
Date:	09/11/2017

Submittal Verification Status	
Prepared By:	
Verified By:	
Signed off by V & V Manager:	
Date:	

The TP2P V&V team has reviewed and assessed the contract documents including Attachment 8 for all Ready for Construction (RFC) submittals.

The TP2P V&V team confirms that, with the inclusion of the Ready for Construction Certification, all comments received during the 90% Design Submittal review, Submittal reference SW04.11.03-034 have been satisfactorily resolved and verified by the Design Lead and are represented in the RFC Submittal herein. The submittal is complete, contains the required documents inclusive of manuals, reports, drawings, procedures, policies, permits, and agreements to demonstrate compliance of this RFC submittal with the Technical Contract Requirements.

TP2P therefore self-certifies the submittal for Guideway Station 9772+35.08 to 10304+00.00 Ready for Construction to be compliant with Contract Requirements and fitness for purpose.

Submittal Certification of Compliance (CoC)

27 2.2.3.6 Operating and Design Speed

28 The CHSR System operating speed shall be 220 mph.

29 In areas of shared-use track, operating speed shall be as follows:

- 30 • Peninsula Corridor from San Francisco to Gilroy: 110 mph
- 31 • Burbank to Anaheim project section in Phase 1 of the project
- 32 • Los Angeles to San Diego in the Phase 2 of the project



33 The System design speed shall be 250 mph.

34 In areas of shared-use track, design speed shall be as follows:

- 35 • Peninsula Corridor from San Francisco to Gilroy: 110 mph
- 36 • Burbank to Anaheim project section in Phase 1 of the project: 125 mph
- 37 • Los Angeles to San Diego in Phase 2 of the project: 125 mph

38 The CHSR System design shall incorporate the needs for a testing speed of at least 110 percent of the

39 operating speed.



Trust but Verify
using **Digital Threads**

SoSE ACTIVITIES PERFORMED

SAFETY REQ. EXAMPLE (CRITICAL ITEM -> CERTIFIABLE ITEMS LIST [CIL])



ID	Hazards & Mitigations	CI	
1	<input checked="" type="checkbox"/> 1 Infrastructure	No	
2	<input checked="" type="checkbox"/> 1.1 R-O-W Generally	No	
12	<input checked="" type="checkbox"/> 1.1.2 Collision	No	
26	<input checked="" type="checkbox"/> 1.1.2.7 Object thrown from overpass	No	
176	<input checked="" type="checkbox"/> 1.1.2.7.1 Mitigation #1	Yes	


[1] TNE:
Install intrusion prevention fencing at overpasses.

Risk of Thrown Objects

Install intrusion prevention fencing at overpasses.




2017Jun28_TLM_LookingNorth.jpg



Design

Construction



SoSE ACTIVITIES PERFORMED

MODULE OF METRIC (MoM) – INSPIRATION

2013 IBM Webinar

Raytheon

Customer Success Is Our Mission



AIR
LAND
SEA
SPACE
CYBER

DOORS® Module of Metrics (MoM) Approach

Jerry Huller

Senior Principal Systems Engineer
15 November 2013

Copyright © 2013 Raytheon Company. All rights reserved.
Customer Success Is Our Mission is a registered trademark of Raytheon Company.


Overview (2 of 3)

Basic concept:

- Create module level DXL attributes that can provide desired data, equivalent to running a simple or compound filter query in DOORS

Create once and copy to all requirement modules


- Use layout DXL to “pull” the attribute values into a master module called the Module of Metrics (MoM), which is accessible at any time by any DOORS user



11/15/2013 | 5

Overview (3 of 3)



Example of MoM view




View	MoM Metrics View-Block	All levels	B1 TotalNumReqs	B1&2 TotalNumTBR	B1 TotalNumHwReqs	TotalNumParentlessReqs
Contains selected metrics data pulled from other modules						
1.1.1	Segment Interface Requirements Specification (IRS) - A028		188	0	41	3
1.1.2	Segment Performance Specification (SPS) - A025		690	1	35	49
1.2.1	GB Element Development Specification (EDS) - A011		421	1	23	0
1.2.2	MZ Element Development Specification (EDS) - A011		465	0	29	0
1.2.3	YS Element Development Specification (EDS) - A011		531	1	24	0

SoSE ACTIVITIES PERFORMED

HIGH-SPEED RAIL MoM





Module of Metrics



SoSE ACTIVITIES PERFORMED

DEFINING THE 100% CONTRACT CERTIFICATION SCOPE (BY QMDP)



Milestones & the Field Engineers responsible for them


GDW01	MADERA COUNTY GUIDEWAY - Litto
GDW02	SIDW TO FRESNO TRENCH GUIDEWAY - Litto
GDW03	N AVENUE C
QMDP 01: GDW01 Guideway Package 01	
NE01	
NE02	SCHMIDT CREEK HST - Katrina
NE03	SCHMIDT CREEK CULVERT BOX - Katrina
NE04	WILDLIFE CROSSING MP167.4 - Katrina
NE05	ROAD 27 - Katrina
NE06	AVE 17 - Katrina
STR01	FRESNO RIVER VIADUCT (FRV) - Gavin
STR02	AVENUE 15-1/2 OH - Katrina
STR03	AVENUE 15 OH - Katrina
STR04	COTTONWOOD CREEK BR - Katrina
STR05	AVENUE 12 HST OH - Katrina
STR06	AVENUE 12 BNSF OH - Katrina

STR 24B	E MUSCAT AVE HST - Gavin
STR25	CENTRAL AVENUE OH - Gavin
STR26	AMERICAN AVENUE OH - Gavin
3RDP001	AT&T - Juan
3RDP002	PG&E - Bianca
3RDP003	CITY OF FRESNO - Bennie
3RDP004	COUNTY OF FRESNO - Bennie
3RDP005	COUNTY OF MADERA - Bennie
3RDP006	UPRR - Addison
3RDP007	BNSF - Addison
3RDP008	CALTRANS - Bennie
3RDP009	MADERA IRRIGATION DISTRICT - Greg
3RDP010	FRESNO IRRIGATION DISTRICT - Greg
3RDP011	FMFCD - Greg
3RDP012	KINDER MORGAN - Addison
3RDP013	LEVE III - Addison
3RDP014	COMCAST - Addison
3RDP015	SPRINT - Addison
3RDP016	TW TELECOM - Addison
3RDP017	TIME WARNER - Addison
3RDP018	QWEST - Addison
3RDP019	CVIN - Addison
3RDP020	SEBATHIAN KERMER TELECOM - Addison
3RDP021	MCI - Addison
3RDP022	SIERRA TELEPHONE - Addison

SYSTEMS ENGINEERING CHALLENGES FACED CONSTRUCTION CERTIFICATION: QUALITY MILESTONE (DATA PACK, QMDP)

Submittal Log

Name	Title	Submittal Type
17699	FCN 227 Avenue 10 HST Box Culvert	INFO
17621	Avenue 10 OH Joint Seal	INFO
17536	Avenue 10 Pavement Remediation Plan	INFO
17469	Avenue 10 OH Construction SSCR	SONO
15564	Eastment T1-091 (AT&T) - Avenue 10	APPROVAL
14656	Avenue 10 OH MSE Structure Pkg	APPROVAL
14435	Avenue 10 HST Box Culvert RFC	APPROVAL
11795	Avenue 10 HST Overhead SSCR	SONO
11774	60% Avenue 10 HST Box Culvert	SONO
11368	RFC Avenue 10 Overhead Design	APPROVAL
10926	Avenue 10 Grade Separation Design	INFO
10814	Avenue 10 Overhead GEDR	SONO
10699	90 Perc Dsgn Avenue 10 OH	SONO
10065	Avenue 8, Avenue 9, and Avenue 10	3RDPARTY



CP1 Structures

CP1: 70+ QMDPs (Quality Milestone Data Packs)

SoSE ACTIVITIES PERFORMED

CP4 EXAMPLE: BUILDING THE MoM



'Module of Metrics' current 1.2 in /CRB DOORS-DB 2021-01/00_Metrics (Formal module) - DOORS

File Edit View Insert Link Analysis Table Tools Discussions User Change Management Help


View 12. MoM Export Level 2

Absolute	Object	_MoM_QMDP	Metrics
54	1		4 Site-Specific Requirements
986	2	QMDP 01	> 4.1 QMDP 01
987	2	QMDP 02	> 4.2 QMDP 02
988	2	QMDP 03	> 4.3 QMDP 03
989	2	QMDP 04	> 4.4 QMDP 04
991	2	QMDP 05	> 4.5 QMDP 05
992	2	QMDP 06	> 4.6 QMDP 06
993	2	QMDP 07	> 4.7 QMDP 07
1050	2	QMDP 08	> 4.8 QMDP 08
994	2	QMDP 09	> 4.9 QMDP 09
995	2	QMDP 10	> 4.10 QMDP 10
996	2	QMDP 11	> 4.11 QMDP 11
997	2	QMDP 12	> 4.12 QMDP 12
998	2	QMDP 13	> 4.13 QMDP 13
999	2	QMDP 14	> 4.14 QMDP 14
1000	2	QMDP 15	> 4.15 QMDP 15
1001	2	QMDP 16	> 4.16 QMDP 16
1002	2	QMDP 17	> 4.17 QMDP 17
1003	2	QMDP 18	> 4.18 QMDP 18
1004	2	QMDP 19	> 4.19 QMDP 19
1005	2	QMDP 20	> 4.20 QMDP 20
1006	2	QMDP 21	> 4.21 QMDP 21
1007	2	QMDP 22	> 4.22 QMDP 22
1008	2	QMDP 23	> 4.23 QMDP 23
1009	2	QMDP 24	> 4.24 QMDP 24
1010	2	QMDP 25	> 4.25 QMDP 25
1011	2	QMDP 26	> 4.26 QMDP 26
1012	2	QMDP 27	> 4.27 QMDP 27
1013	2	QMDP 28	> 4.28 QMDP 28



**Contractor
QMDP Plan**

#	Activity ID	QMDP #	Activity Name	Stationing	Responsible
1	MIL_1285	QMDP 01	EOP to County Line	14769+23 - 14822+00	North S.M.
2	MIL_1290	QMDP 02	County Line to S Scofield	14822+00 - 14877+00	North S.M.
3	MIL_1295	QMDP 03	S Scofield to Garces Abut1	14877+00 - 14931+21	North S.M.
4	MIL_1145	QMDP 04	Garces Hwy Underpass	14931+31 - 14932+23	North S.M.
5	MIL_1300	QMDP 05	Garces Abut. 2 to Woollomes Ave	14932+23 - 14989+50	North S.M.
6	MIL_1305	QMDP 06	Woollomes Ave to Pump Station	14989+50 - 15055+00	North S.M.
7	MIL_1310	QMDP 07	Pump Stat ion to S. Magnolia	15055+00 - 15096+50	North S.M.
8	MIL_1315	QMDP 08	S. Magnolia to Pond Rd. Abut. #1		
9	MIL_1115	QMDP 09	Pond Rd Underpass		
10	MIL_1320	QMDP 10	Pond Rd. Abut. 2 to Peterson Rd. A		
11	MIL_1155	QMDP 11	Peterson Rd Underpass		
12	MIL_1325	QMDP 12	Peterson Rd. Abut. 1 to Elmo Hwy		
13	MIL_1330	QMDP 13	Elmo Hwy to Sherwood Ave		
14	MIL_1335	QMDP 14	Sherwood Ave to Poso Creek Abut		
15	MIL_1105	QMDP 15	Poso Creek Overpass		
16	MIL_1340	QMDP 16	Poso Creek Abut. 1 to Taussig Ave.		
	MIL_1345	QMDP 17	Taussig Ave to Canal 9-22		
	MIL_1350	QMDP 18	Canal 9-22 to McCombs Ave.		
	MIL_1185	QMDP 19	McCombs Ave Overpass		
20	MIL_1355	QMDP 20	McCombs Ave.to SR-46 Abut. 1		
21	MIL_1095	QMDP 21	SR 46 Underpass	15560+89 - 15562+12	South S.M.
22	MIL_1360	QMDP 22	SR-46 Abut. 1 to Pedestrian Underpass	15563+00 - 15587+00	South S.M.
23	MIL_1085	QMDP 23	HST Pedestrian Underpass	15588+25 - 15590+25	South S.M.
24	MIL_1365	QMDP 24	Pedestrian Underpass to Poso Ave	15590+00 - 15614+00	South S.M.
25	MIL_1195	QMDP 25	Poso Ave Underpass	15613+83 - 15614+43	South S.M.
26	MIL_1370	QMDP 26	Poso Ave to Wasco Viaduct Abut. 1	15614+00 - 15660+00	South S.M.
27	MIL_1270	QMDP 27	Wasco Viaduct	15660+20 - 15679+73	South S.M.
28	MIL_1375	QMDP 28	Wasco Viaduct Abutment 11 to Kimber	15660+00 - 15720+00	South S.M.



SoSE ACTIVITIES PERFORMED

CP4 EXAMPLE: SUBMITTALS BY QMDP, MEASURING PROGRESS



'Module of Metrics' current 1.2 in /CRB DOORS-DB 2021-01/00_Metrics (Formal module) - DOORS

File Edit View Insert Link Analysis Table Tools Discussions User Change Management Help

View 12. MoM Export Level 7

Absolute	Object	_MoM_QMDP	Metrics	_MoM_RDC	_MoM_HSR_3RD	Submittal Date	SONO/APP Date	Linked Module	Linked O
54	1		4 Site-Specific Requirements						
989			4.4 QMDP 04						
1			Design Submittals						
1			High-Speed Rail		HSR				
1			4.4.1.1 HSR Aerial Structure		HSR				
1			4.4.1.1.1 Garces		HSR				
7			4.4.1.1.1.1 Design	Design	HSR				
2			Type Selection Report (TSR)	Design	HSR	05 June 2017	16 June 2017	01 Civil Evidence Module	5.2 TSI
2			Geotechnical Engineering Design Report (GEDR)	Design	HSR	23 January 2019	27 April 2017	01 Civil Evidence Module	5.1 GEI
2			60% Design	Design	HSR	19 June 2017	06 November 2017	01 Civil Evidence Module	5.3 60%
2			90% Design	Design	HSR	18 December 2017	26 February 2018	01 Civil Evidence Module	5.4 90%
5			Ready for Construction (RFC)	Design	HSR	12 March 2019	19 November 2018	01 Civil Evidence Module	5.5 RFC
3			Bearings: Design Calcs	Design	HSR	22 January 2019	23 May 2019	01 Civil Evidence Module	19.1 G
799	6	QMDP 04	4.4.1.1.1.2 Construction	Construction	HSR				
1			Construction Stage 1: Foundations, Abutments & Bents	Construction	HSR			01 Civil Evidence Module	5.6.1 S
3			Construction Stage 2: Wingwall & Approaches	Construction	HSR			01 Civil Evidence Module	5.6.2 S
3			Construction Stage 3, 4, 5: Superstructure	Construction	HSR			01 Civil Evidence Module	5.6.3 S
1			2 Third Parties						
1			4.4.2.1 Electric Distribution						
7			4.4.2.1.1 Conflict 12004, PG&E						
1			4.4.2.1.1.1 Design	Design					
4			Issued for Construction (IFC)	Design		August 2018	29 August 2018	02 Utility Evidence Module	2.92 IF
1			4.4.2.1.1.2 Construction	Construction					
7			Construction: All Stages	Construction					
113			4.4.2.2 Telecom						
813	5	QMDP 04	4.4.2.2.1 Conflict 1000, AT&T						
1151	6	QMDP 04	4.4.2.2.1.1 Design	Design	Third Party				
389	7	QMDP 04	Ready for Construction (RFC)	Design	Third Party			02 Utility Evidence Module	1.30 RF
1152	6	QMDP 04	4.4.2.2.1.2 Construction	Construction	Third Party				

Planned Work

Completed Work

Submittal Dates

Acceptance Dates

Information Retrieved from Contractor RM Tool Database

Achieved Progress

Design Submittals

Construction Submittals

SoSE ACTIVITIES PERFORMED

CP4 EXAMPLE: USING THE DIGITAL THREADS




'Module of Metrics' current 1.2 in /CRB DOORS-DB 2021-01/00_Metrics (Formal module) - DOORS

File Edit View Insert Link Analysis Table Tools Discussions User Change Management Help

View 12. MoM Export All levels


Absolute	Object	_MoM_QMDP	Metrics
54	1		4 Site-Specific Requirements
989	2	QMDP 04	4.4 QMDP 04
1133	3	QMDP 04	4.4.1 High-Speed Rail
130	4	QMDP 04	4.4.1.1 HSR Aerial Structure
181	5	QMDP 04	4.4.1.1.1 Garces
798	6	QMDP 04	4.4.1.1.1.1 Design
247	7	QMDP 04	Type Selection Report (TSR)
248	7	QMDP 04	Geotechnical Engineering Design Report (GEDR)
628	8	QMDP 04	SS.AS.GARCES.GEDR.RVTM
627	8	QMDP 04	SS.AS.GARCES.GEDR.CIL
249	7	QMDP 04	60% Design
250	7	QMDP 04	90% Design
55	7	QMDP 04	Ready for Construction (RFC)
15	8	QMDP 04	SS.AS.GARCES.RFC.RVTM
14	8	QMDP 04	SS.AS.GARCES.RFC.CIL
807	8	QMDP 04	SS.AS.GARCES.RFC.COC
349	7	QMDP 04	Bearings: Design Calcs
88	8	QMDP 04	SS.AS.GARCES.BEA.RVTM

California High-Speed Rail Construction Package 4			
	V&V Report for RFC Design Drawings for HSR Structure over Garces Highway	Revision:	04
	Doc No.: CP4-6.16.2.1-0002	Date:	3/12/2019

2. CERTIFICATE OF COMPLIANCE WITH TECHNICAL CONTRACT REQUIREMENTS

This certification of compliance includes the confirmation by the Contractor's V&V Manager, as per the VVSC section 2.3.4 and 3.1, that the work described in this submittal is in compliance with the Technical Contract Requirements and fitness for purpose and that the references to the objective evidence provided in the RVTM checked by the Contractors QA/QC process, and have been confirmed as

Certificate of Compliance (CoC)



Design Submittals

01 Civil Evidence Module	5.2 TSF
01 Civil Evidence Module	5.1 GED
01 GEDR Garces_RVTM	-
01 GEDR Garces_CIL	-

'01 RFC Garces_RVTM' current 3.4 in /CRB DOORS-DB 2021-01/40_V V Civil Design Submittals/06 RFC Submittals/02 HST Aerial Structure (Formal module) - DOORS


File Edit View Insert Link Analysis Table Tools Discussions User Change Management Help

TID	RVTM ID	Document Name	Requirements Section	Requirements Text	Submittal PMT	RAM	In Compliance with Contract Documents	Reference Document	DCN
30	DCM.01.47	01 DCM CH01	1.2.1 Infrastructure	Fully grade-separated crossings	Design Baseline Report HST A-Grade (Guideway) HST Aerial Structure and/or Bridge HST Open Trench HST Cut & Cover Tunnel		Verified	ST-K1001-GAR Elevation	
45	DCM.01.62	01 DCM CH01	1.2.5 Design and Operating Speeds	A design speed of 250 mph is required where cost-effective and where topographic, geometric, operational, and environmental conditions permit. The design shall allow for sustained operating speed of 220 mph.	Design Baseline Report HST A-Grade (Guideway) HST Aerial Structure and/or Bridge HST Open Trench HST Cut & Cover Tunnel Report and/or Calculation		Verified	ST-K0003-GAR Gen. Notes	
169	DCM.01.186	01 DCM CH01	1.3.4.1 Precedence by Jurisdiction	Where Third Party infrastructure is located within the Authority's right-of-way, the more stringent of the requirements shall apply as required to achieve concurrence of the Authority and Third Party.	Design Baseline Report Report and/or Calculation Specification		Verified	St-K1001 Plan	
179	DCM.01.196	01 DCM CH01	1.4.1 Units of Measurement	The CHST system shall be based on U.S. Customary Units, defined by the National Institute of Standards and Technology (NIST). This is consistent with guidelines prepared by Caltrans.	Design Baseline Report HST A-Grade (Guideway) HST Aerial Structure and/or Bridge HST Open Trench HST Cut & Cover Tunnel RDW Underpass (HST Overpass) RDW Overhead (HST Underpass) Report and/or Calculation Specification		Verified	CAD Manual, Section 1.3.5	
181	DCM.01.198	01 DCM CH01	1.4.1 Units of Measurement	Design and construction drawings shall be developed in accordance with the CHSTP CADD Manual.	Design Baseline Report HST A-Grade (Guideway) HST Aerial Structure and/or Bridge HST Open Trench HST Cut & Cover Tunnel RDW Underpass (HST Overpass) RDW Overhead (HST Underpass) Report and/or Calculation Specification		Verified	CAD Manual, Section 1.3.5	
18				defined in the CHSTP Plan	Design Baseline Report HST A-Grade (Guideway) HST Aerial Structure and/or Bridge		Verified	Milepost is shown in bridge identifier FID in all the sheets. FID	

Requirements Verification Traceability Matrix (RVTM)

SoSE ACTIVITIES PERFORMED

CP4 EXAMPLE: REPORTING CERTIFICATES OF COMPLIANCE (CoC) PROGRESS



Metrics' current 1.2 in /CRB DOORS-DB 2021-01/00_Metrics (Formal module) - DOORS

File Edit View Insert Link Analysis Table Tools Discussions User Change Management Help

CERT: DES & HSR | All levels | View 07. MoM CERT: CONST (QM | All levels | _MoM_HSR_3RD

_MoM_QMDP#	Metrics	MoM View(s)	Absolute	Object	_MoM_QMDP#	Metrics	_MoM_HSR_3RD
	3 General & Typical Requirements		14	1		4 Site-Specific Requirements	
GEN / TYP	3.1 CP4 Wide (General)		986	2	QMDP 01	4.1 QMDP 01	
GEN / TYP	3.1.1 High-Speed Rail		1133	3	QMDP 01	4.1.1 High-Speed Rail	HSR
GEN / TYP	3.1.1.1 Baseline Reports					4.1.1.1 HSR At-Grade	HSR
GEN / TYP	3.1.1.1.2 Final Design Report					4.1.1.1.1 North	HSR
GEN / TYP	3.1.1.1.2.2 Design					4.1.1.1.1.2 Construction	HSR
GEN / TYP	Final Design Report					Construction Stage 4: Access	HSR
GEN / TYP	CP4.BL.FDR.COC					SS.AG.NORTH.QMDP01.CS4.COC	HSR & Third Party
GEN / TYP	3.1.1.1.4 RAM Reports					QMDP 02	
GEN / TYP	3.1.1.1.4.5 Final Maintenance Concept					4.2.1 High-Speed Rail	HSR
GEN / TYP	3.1.1.1.4.5.2 Design					4.2.1.1 HSR At-Grade	HSR
GEN / TYP	Final Maintenance Concept					4.2.1.1.1 North	HSR
GEN / TYP	CP4.RAM.FMC.COC					4.2.1.1.1.2 Construction	HSR
GEN / TYP	3.1.1.1.4.6 Maintenance Manual					Construction Stage 4: Access	HSR
GEN / TYP	3.1.1.1.4.6.2 Design					SS.AG.NORTH.QMDP02.CS4.COC	HSR & Third Party
GEN / TYP	Maintenance Manual					QMDP 03	
GEN / TYP	CP4.RAM.MM.COC					4.3.1 High-Speed Rail	HSR
GEN / TYP	3.1.1.1.4.7 Maintainability Demonstration Test Plan and Procedure					4.3.1.1 HSR At-Grade	HSR
GEN / TYP	3.1.1.1.4.7.2 Design					4.3.1.1.1 North	HSR
GEN / TYP	Maintainability Demonstration Test Plan and Procedure					4.3.1.1.1.2 Construction	HSR
GEN / TYP	CP4.RAM.MDTP.COC					Construction Stage 4: Access	HSR
GEN / TYP	3.1.1.1.4.8 Maintainability Demonstration Test Report (MDTR)					SS.AG.NORTH.QMDP03.CS4.COC	HSR & Third Party
GEN / TYP	3.1.1.1.4.8.2 Design					4.4 QMDP 04	
GEN / TYP	Maintainability Demonstration Test Report					4.4.1 High-Speed Rail	HSR
GEN / TYP	CP4.RAM.MDTR.COC					4.4.1.1 HSR Aerial Structure	HSR
GEN / TYP	3.2 Typical Design Elements / Typical Detail					4.4.1.1.1 Garces	HSR
GEN / TYP	3.2.1 High-Speed Rail					4.4.1.1.1.2 Construction	HSR
GEN / TYP	3.2.1.1 Structural Elements						

SoSE ACTIVITIES PERFORMED

CP4 EXAMPLE: SAFETY & SECURITY CERTIFICATION REPORTS (SSCR) PROGRESS



'Module of Metrics' current 1.2 in /CRB DOORS-DB 2021-01/00_Metrics (Formal module) - DOORS

File Edit View Insert Link Analysis Table Tools Discussions User Change Management Help

View 08. MoM S&S: CONST (SSC) All levels

Absolute	Object	_MoM_QMDP#	Metrics	_MoM_HSR_3RD	_MoM_RDC	_MoM_Cert	Submittal Date	SONO/APP Date	Linked Module
54	1		4 Site-Specific Requirements						
986	2	QMDP 01	4.1 QMDP 01						
1153	3	QMDP 01	4.1.1 High-Speed Rail	HSR					
6	4	QMDP 01	4.1.1.1 HSR At-Grade	HSR					
46	5	QMDP 01	4.1.1.1.1 North	HSR					
797	6	QMDP 01	4.1.1.1.1.2 Construction	HSR	Construction				
315	7	QMDP 01	Construction Stage 4: Access	HSR	Construction				01 Civil Evidence Module
3358	8	QMDP 01	SS.AG.NORTH.QMDP01.CS4.SSCR	HSR & Third Party	Construction				
989	2	QMDP 04	4.4 QMDP 04						
1133	3	QMDP 04	4.4.1 High-Speed Rail	HSR					
130	4	QMDP 04	4.4.1.1 HSR Aerial Structure	HSR					
181	5	QMDP 04	4.4.1.1.1 Garces	HSR					
799	6	QMDP 04	4.4.1.1.1.2 Construction	HSR					
321	7	QMDP 04	Construction Stage 3, 4, 5: Superstructure	HSR					
3364	8	QMDP 04	SS.AS.GARCES.QMDP04.CS3.SSCR	HSR & Third Party					
993	2	QMDP 07	4.7 QMDP 07						
1163	3	QMDP 07	4.7.1 High-Speed Rail	HSR					
1032	4	QMDP 07	4.7.1.1 HSR At-Grade	HSR					
1061	5	QMDP 07	4.7.1.1.1 North	HSR					
1063	6	QMDP 07	4.7.1.1.1.2 Construction	HSR					
1647	7	QMDP 07	Construction Stage 4: Access	HSR					
3359	8	QMDP 07	SS.AG.NORTH.QMDP07.CS4.SSCR	HSR & Third Party					
994	2	QMDP 09	4.9 QMDP 09						
1167	3	QMDP 09	4.9.1 High-Speed Rail	HSR					
990	4	QMDP 09	4.9.1.1 HSR Aerial Structure	HSR					
133	5	QMDP 09	4.9.1.1.1 Pond	HSR					
845	6	QMDP 09	4.9.1.1.1.2 Construction	HSR	Construction				

MoM View(s)

CHSRs: CONTRACT VS. SYSTEM CERTIFICATION

SYSTEM IS SAFE, SECURE AND READY TO OPERATE



❖ Introduction

- Brief System of Systems (SoS) Overview
- California High-Speed Rail System (CHSRS) Program
- Use of Digital Threads in the CHSRS Program

❖ SoSE Challenges Faced

- Systems Engineering Challenges
- SoS Engineering Challenges

❖ SoSE Activities Performed

- Certification Strategy
- Step by Step Process Description

❖ Summary, Achieved Outcomes & Conclusion

[illegible]

The diagram shows a central image of a train on tracks. Above the train are two boxes labeled "Interfacing Systems & Organization" connected by a double-headed arrow. Below the train, a dashed line encloses a flow diagram. On the left, a light blue box labeled "Program Level (SoS)" has a "SYSTEM OF SYSTEM" box below it. Arrows point from this box to three yellow boxes labeled "Project #1 (Constituent System)", "Project #2 (Constituent System)", and "Project #n (Constituent System)". A "CONSTITUENT SYSTEMS" box is positioned between Project #1 and Project #2. Arrows from all three project boxes point to a light green box on the right labeled "Program Level (SoS)", which has a "SYSTEM OF SYSTEM" box below it.

The diagram illustrates the project lifecycle for a high-speed rail project, organized into a grid with phases (Program, Preliminary, Final, Construction, Contract, Integration, System) and stages (Environmental Review, Final Design, Final Integration, Revenue Service). The central flow shows the progression from a 'Desired System' through various engineering and construction stages to an 'Operated System'. Key milestones include 'Contract Certification Acceptance & Handover' and 'Objective Evidence' collection. A timeline at the bottom indicates the sequence of these phases.

Phases and Stages:

- Program:** Environmental Review & Preliminary Engineering
- Preliminary:** Final Design & Construction (Design, Bid.) Build, P3
- Final:** Final Integration, Testing & Certification
- Construction:** Revenue Service
- Contract:** Contract Certification Acceptance & Handover
- Integration:** Objective Evidence
- System:** Operated System

Key Milestones and Deliverables:

- Desired System:** Represented by an image of a train.
- Program Planning, urban & socioeconomic analysis:** A funnel-shaped diagram.
- Infrastructure Engineering for Procurement:** A box.
- Contract Packaging:** A box.
- Design:** Represented by an image of a bridge.
- Construction:** Represented by an image of a train.
- Contract Certification Acceptance & Handover:** A box.
- Objective Evidence:** A box containing images of a train and a document.
- Transfer to operations:** A box.
- Operated System:** Represented by an image of a train.
- Operations & Maintenance:** A box.
- System performance:** A box.

Timeline:

PROGRAM | PRELIMINARY | FINAL | CONSTRUCTION | CONTRACT | INTEGRATION, TESTING | SYSTEM

[illegible]

The diagram illustrates the system engineering challenges faced by various stakeholders across six stages of a project. Each stage is represented by a box with a title and a list of challenges. The stages are: Contract, Step 1 Contract Requirements, Step 2 Technical Contract Requirements (TCR), Step 3 Type Requirements, Step 4 Site-Specific Requirements, Step 5 Submittal-Specific Requirements (NTH), and Step 6 Objective Evidence. The stakeholders involved are: Contract Documents, TCR Author, Techn. Contract Requirements, Alloc. Author, General / Typical Requirements, Site Alloc. Author, Site-Specific Requirements, Submit Alloc. Author, Submittal-Specific Requirements (NTH), and Objective Evidence. The challenges are: Contract Documents, TCR Author, Techn. Contract Requirements, Alloc. Author, General / Typical Requirements, Site Alloc. Author, Site-Specific Requirements, Submit Alloc. Author, Submittal-Specific Requirements (NTH), and Objective Evidence. The challenges are: Contract Documents, TCR Author, Techn. Contract Requirements, Alloc. Author, General / Typical Requirements, Site Alloc. Author, Site-Specific Requirements, Submit Alloc. Author, Submittal-Specific Requirements (NTH), and Objective Evidence.

Drawing # Drawing Name

Drawing #	Drawing Name	Rev	Page #
G2-00001	COVER SHEET	0	1
TT-00001	TRACK GUIDEWAY - HORIZONTAL ALIGNMENT DATA TABLE	0	8
TT-E6001	TRACK CHART - SHEET 1 OF 13	0	9
TT-E6002	TRACK CHART - SHEET 2 OF 13	0	10
TT-E6003	TRACK CHART - SHEET 3 OF 13	0	11

Digital Thread

Submittal Certification of Compliance (CoC)

Page 9 of 340

250 MPH

250 MPH

250 MPH

Drawing TT-E6001

37

[illegible][illegible]

ACHIEVED OUTCOMES & CONCLUSION



❖ Large System of Systems

- SoS Authority & Leadership: Program verification, validation & certification approach with tailored project type implementation (i.e., civil works, track and systems, trainsets, etc.)
- SoS Architecture: Program as SoS with projects as constituent systems
- SoS Autonomous Constituent Systems & Emergence: Projects as black box with defined interfaces: inputs (requirements) & outputs (construction certifications)

❖ Use of Digital Threads enables Convenient Access to:

- Technical contract requirements and critical items (i.e., RVTMs, CILs)
- Design & construction submittals and individual submittal files (drawings, calculations, etc.)
- Design & construction certifications (e.g., CoCs)
- Safety and security certifications (e.g., SSCRs)

❖ System Certification

- Trust but verify: Provision of certifications and supporting objective evidence

❖ Conclusion

- Verification, validation & certification provides high transparency and trust that the final California High-Speed Rail System will be **Safe, Secure, and Ready to Operate**.



32nd Annual **INCOSE**
international symposium

hybrid event

Detroit, MI, USA
June 25 - 30, 2022

www.incose.org/symp2022